


## MEMORANDUM

---

FILE:PROJ/SVCSD TERTIARY TREATMENT  
UPGRADE PROJECT 70-12-7 #30

**DATE:** JUNE 8, 2006

**TO:** PLANHOLDERS

**FROM:** DALE ROBERTS  PROJECT MANAGER

**SUBJECT:** SONOMA VALLEY COUNTY SANITATION DISTRICT (SVCSD) TERTIARY  
TREATMENT UPGRADE PROJECT - SUBSTITUTION REQUEST FOR  
KRUGER HYDROTECH DISCFILTER TERTIARY FILTER

Attached are the completed Document 00660 (Substitution Request Form) for the subject substitution request and the Owner's remarks to the request.

**SONOMA VALLEY COUNTY SANITATION DISTRICT (SVCSD)  
TERTIARY TREATMENT UPGRADE PROJECT  
REMARKS TO SUBSTITUTION REQUEST FORM FOR  
KRUGER HYDROTECH DISCFILTER TERTIARY FILTER**

FILE:PROJ/SVCSD TERTIARY TREATMENT  
UPGRADE PROJECT 70-12-7 #30

SVCSD has reviewed the Substitution Request submitted by I. Kruger, Inc. for Hydrotech Discfilter as acceptable equipment under Section 11212 – Tertiary Filters (Option C).  
SVCSD has determined that the Hydrotech Discfilter is accepted as noted below.

1. Tertiary filtration system shall meet requirements of Section 11212 and maintain the same operational functionality as Tertiary Filter (Option A) and Tertiary Filter (Option B). Operational functionality of these tertiary filtration systems includes but is not limited to the following:
  - a. Continuous metering of backwash return;
  - b. Ability to isolate each filtration cell and recirculate a chemical solution through or across the filter media of the isolated cell while all other filtration cells remain in service.
2. Four Discfilter Model HSF2216-2F tertiary filters (three duty, one standby) must be provided.
3. As per paragraph 11212-1.4.A, Contractor must provide revised design drawings for all drawings pertaining to the tertiary filtration system during submittal review. Owner will furnish to the Contractor all AutoCAD drawings used to prepare the Bid Documents. At a minimum, the drawings (whether designated "A" or "B") requiring revision would be: G-4, C-3, C-4, C-5, C-6, C-7, C-11, SP-4, SP-5, SP-6, SP-7, SP-8, SP-9, SP-10, SP-11, SP-16, E-3, E-4, E-5, E-6, and E-9.

## DOCUMENT 00660

## SUBSTITUTION REQUEST FORM

During Bid Period To: Dale Roberts, P.E. Sonoma Valley County Sanitation District Fax: 707-524-3782	After Award of Contract To: Mathew Vail, Construction Management Sonoma Valley County Sanitation District Fax: 707-524-3791
--	--

Project: Tertiary Treatment Plant UpgradeBidder: N/ASubcontractor/Supplier: KrugerDrawing Sheet Reference/Detail No: Alternative B Drawings

The undersigned Bidder submits for consideration the following equipment instead of the specified item for the above Project:

<u>Section</u>	<u>Paragraph</u>	<u>Specified Item</u>
<u>11212</u>	<u>All</u>	<u>Alternative Filtration System</u>
<u> </u>	<u> </u>	<u> </u>

Proposed Substitution: Hydrotech Discfilter

The undersigned encloses the information required herein. If this Document 00660 is being submitted by a Bidder wishing to use "equal" item(s) as provided in Document 00200 (Instructions to Bidders), the undersigned Bidder must also enclose the technical information (other than cost) otherwise required for a post-Award of Contract Request for Substitution ("RFS") under Section 01600 (Product Requirements). However, if this Document 00660 is being submitted under provisions of Contract Documents after Award of Contract, the undersigned Contractor must include all information required under Section 01600 (Product Requirements).

The undersigned has (a) attached manufacturer's literature, including complete technical data and laboratory test results, if applicable, (b) attached an explanation of why proposed substitution is a true equivalent to specified item, (c) included complete information on changes to Contract Documents that the proposed substitution will require for its proper installation, and (d) filled in the blanks below:

A. Does the substitution affect dimensions shown on Drawings? (If yes, please explain)

Yes. See attached information package.

- B. Are the manufacturer's guarantees and warranties on the proposed substitution items identical to those on the specified items? If there are differences, please specify each and every difference in detail.

Yes

- C. What effect does the substitution have on other contractors, trades, or suppliers?

None

- D. What are the differences between the proposed substitution and the specified item? If proposed substitution has a color or pattern, provide a color board showing proposed substitution in relation to the other adjacent colors and patterns.

Yes. See attached information package per Section 01600.

- E. Will granting the requested substitution cause any schedule delay? (If yes, please explain)

None

The undersigned Bidder certifies that the function, appearance, and quality of the proposed substitution are equivalent or superior to those of the specified item.

Submitted by:

I. KRUGER INC.

Bidder

M. J. Hunter

Signature

M. TODD HATHAWAY

Name

401 HARRISON OAKS BLVD SUITE 100

Address

CADIZ, MI 49813

City/State/Zip

Telephone: 919-677-8310

Date: 5/25/06

For Use by Owner:

☐ Accepted

☒ Accepted as Noted

☐ Not Accepted

☐ Received Too Late

By: [Signature]

Owner's Representative

Date: 06 JUNE 2006

Remarks: SEE ATTACHED

MEMO.

END OF DOCUMENT





401 Harrison Oaks Blvd  
Suite 100  
Cary, NC 27513  
Phone (919) 677-8310  
Fax (919) 677-0082

**Fax**

**Location:** I. Kruger Inc.

**Pages 1 of** MANY

**Date:** 5/25/06

**To:** MR. DALE ROBERTS, P.E.

**Company:** Sonoma Valley County <sup>Sanitation</sup> District

**Fax:** 707-524-3782

**Tel:**

**From:** TODD HATHAWAY

**C.C.:** FILE

**Subject:** SUCSD TERTIARY TREATMENT PLANT UPGRADE  
KRUGER DISINFECTANT SUBSTITUTION REQUEST INFORMATION.

MR. ROBERTS,

I APOLOGIZE FOR THE DELAY AND THE MANNER IN WHICH I AM  
SUBMITTING THIS INFORMATION. KRUGER DID NOT RECEIVE THE BIDDING  
DOCUMENTS UNTIL TODAY. I AM FAXING YOU A VERY LARGE  
PACKAGE (AS LISTED ON FORM 00660). I WILL ALSO OVERNIGHT  
YOU ~~the~~ A COPY FOR YOUR RECORDS. PLEASE CALL WITH  
QUESTIONS.

THANK YOU!

M. J. Hathaway  
PRODUCT MANAGER

THIS TRANSMISSION CONTAINS CONFIDENTIAL INFORMATION INTENDED FOR USE ONLY  
BY THE ABOVE NAMED RECIPIENT. READING, DISCUSSION, DISTRIBUTION, OR COPYING OF  
THIS MESSAGE IS STRICTLY PROHIBITED BY ANYONE OTHER THAN THE NAMED RECIPIENT  
OR HIS OR HER EMPLOYEES OR AGENTS. IF YOU HAVE RECEIVED THIS FAX IN ERROR,  
PLEASE IMMEDIATELY NOTIFY US BY TELEPHONE (COLLECT), AND RETURN THE ORIGINAL  
MESSAGE TO US AT THE ABOVE ADDRESS VIA U.S. POSTAL SERVICE.





**SVCSD TERTIARY TREATMENT  
PLANT UPGRADE**

**SUBSTITUTION REQUEST  
PACKAGE**

# SVCSD TERTIARY TREATMENT PLANT UPGRADE SUBSTITUTION REQUEST

## TABLE OF CONTENTS

(Per Section 01600 – 1.3.D)

- A. DOCUMENT 00660 – SUBSTITUTION REQUEST FORM
- B. PRODUCT IDENTIFICATION
- C. MANUFACTURER'S LITERATURE
  - 1) PRODUCT BROCHURE
  - 2) DRIVE MOTOR INFO – SEW EURODRIVE
  - 3) BACKWASH PUMP INFO – GRUNDFOS PUMP
- D. INSTALLATION LIST
- E. MANUFACTURER'S REPRESENTATIVE INFO
- F. CONSTRUCTION METHODS
- G. EQUIPMENT VARIATION DETAILS
  - 1) SAMPLE DRAWINGS
  - 2) MAINTENANCE REQUIREMENTS
  - 3) FUNCTIONAL DIFFERENCES
  - 4) AVAILABLE REPAIR AND REPLACEMENT SERVICES

A. DOCUMENT 00660 – SUBMISSION REQUEST FORM

DOCUMENT 00660

## SUBSTITUTION REQUEST FORM

During Bid Period To: Dale Roberts, P.E. Sonoma Valley County Sanitation District Fax: 707-524-3782	After Award of Contract To: Mathew Vail, Construction Management Sonoma Valley County Sanitation District Fax: 707-524-3791
--	--

Project: Tertiary Treatment Plant UpgradeBidder: N/ASubcontractor/Supplier: KrugerDrawing Sheet Reference/Detail No: Alternative B Drawings

The undersigned Bidder submits for consideration the following equipment instead of the specified item for the above Project:

<u>Section</u>	<u>Paragraph</u>	<u>Specified Item</u>
<u>11212</u>	<u>All</u>	<u>Alternative Filtration System</u>

Proposed Substitution: Hydrotech Discfilter

The undersigned encloses the information required herein. If this Document 00660 is being submitted by a Bidder wishing to use "equal" item(s) as provided in Document 00200 (Instructions to Bidders), the undersigned Bidder must also enclose the technical information (other than cost) otherwise required for a post-Award of Contract Request for Substitution ("RFS") under Section 01600 (Product Requirements). However, if this Document 00660 is being submitted under provisions of Contract Documents after Award of Contract, the undersigned Contractor must include all information required under Section 01600 (Product Requirements).

The undersigned has (a) attached manufacturer's literature, including complete technical data and laboratory test results, if applicable, (b) attached an explanation of why proposed substitution is a true equivalent to specified item, (c) included complete information on changes to Contract Documents that the proposed substitution will require for its proper installation, and (d) filled in the blanks below:

A. Does the substitution affect dimensions shown on Drawings? (If yes, please explain)

Yes. See attached information package.

- B. Are the manufacturer's guarantees and warranties on the proposed substitution items identical to those on the specified items? If there are differences, please specify each and every difference in detail.

Yes

- C. What effect does the substitution have on other contractors, trades, or suppliers?

None

- D. What are the differences between the proposed substitution and the specified item? If proposed substitution has a color or pattern, provide a color board showing proposed substitution in relation to the other adjacent colors and patterns.

Yes. See attached information package per Section 01600.

- E. Will granting the requested substitution cause any schedule delay? (If yes, please explain)


None

The undersigned Bidder certifies that the function, appearance, and quality of the proposed substitution are equivalent or superior to those of the specified item.

Submitted by:

I. KRUGER INC.

Bidder



Signature

M. TODD HATHAWAY

Name

401 HARRISON OAKS BLVD. SUITE 100

Address

CARY, NC 27513

City/State/Zip

Telephone: 919-677-8310

Date: 5/25/06

For Use by Owner:

☐ Accepted ☐ Accepted as Noted

☐ Not Accepted ☐ Received Too Late

By: \_\_\_\_\_  
Owner's Representative

Date: \_\_\_\_\_

Remarks: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

END OF DOCUMENT

## B. PRODUCT IDENTIFICATION

### HYDROTECH DISCFILTER

---

<b>Number of Discfilter units:</b>	4 (3 duty, 1 standby)
<b>Discfilter Model:</b>	HSF2216-2F
<b>Drum:</b>	
Material	SS304
<b>Disc:</b>	
Material	ABS
<b>Filter element:</b>	
Frame material	SS304
Filter media	Woven Polyester
Filter pore size, $\mu\text{m}$	10
Number of discs installed per unit	16
Total filter area, $\text{ft}^2$	964
Submerged filter area, $\text{ft}^2$	627
<b>Drive system:</b>	
Gearbox and motor manufacturer	SEW Eurodrive
Filter motor	1.5 hp, 480V, 3-phase, 60Hz
<b>Back-wash pump:</b>	
Rinse water pump type	Grundfos
Pump motor	15 hp, 480V, 3-phase, 60Hz
Capacity at 110 psi	106 gpm
<b>Covers:</b>	
Material	Aluminum
<b>Tank:</b>	
Material	Concrete basins (provided by others)

---

C. MANUFACTURER'S LITERATURE





# Hydrotech Discfilter

Filtration Made  
Simple

# Hydrotech Discfilter

THE STURDY AND COMPACT  
TITLE 22 APPROVED  
HYDROTECH DISCFILTER IS  
A GREAT CHOICE FOR:


- Effluent Polishing of Wastewater
- Water Reclamation and Reuse
- Product Recovery
- Process Water Filtration
- Other Applications Requiring Space Saving Filters with Fine Filter Openings and a Large Filter Area

The Hydrotech Discfilter is an ideal filtration system for fine solids removal and product recovery


By employing woven cloth filter elements installed on multiple discs, the Hydrotech Discfilter supplies a large filter area within a small footprint.

The Hydrotech Discfilter allows for the minimization of mechanical and other ancillary equipment. The components requiring periodic maintenance are easily accessible from outside the filter. The filter's materials of construction ensure durability under the toughest conditions to allow for a trouble-free operation.


The Hydrotech Discfilter has the flexibility of being composed of 304 or 316 stainless steel. Furthermore, it supplies a large filter area within a small footprint that is up to 75% smaller than a traditional sand filter. The Hydrotech Discfilter is a cost-effective alternative to other technologies.



*Concrete Installation*



*Tank Installation*



The 2200 series Discfilter, which includes all of the standard Hydrotech benefits, is tailored for tertiary treatment applications.



### Partial Submergence

Filtering at partial submergence allows multiple operational benefits. The effluent collection tank does not need to be drained to clean the Discfilter since the backwash cleaning system is above the submergence level. Additionally, flow through the filter is continuous, even during a backwash cleaning cycle the filter never goes off line. This arrangement also allows for the effective removal of large solids and floatables.

### Moving Backwash Spray Header


The moving backwash spray header of the Hydrotech Discfilter guarantees efficient cleaning of the filter media. This feature increases the life expectancy of the filter media and results in a 20% savings in rinse water consumption. The backwash spray header also folds out to facilitate maintenance of the spray nozzles, which can be removed and replaced without the use of any tools.

### Modular Filter Panels

The modular filter panels consist of a woven polyester filter media, which is held within a stainless steel frame. With a precise pore size, the woven material of the Discfilter media allows for better filtration than filters containing non-woven media with an "average" pore size. The woven filter media is available in various pore sizes up to 1 mm.

### Filter Expansion

The modular panels provide a simple means of maintaining and expanding the Discfilter. The largest filter can contain up to 20 discs; however, a filter containing fewer discs can be installed with more discs added as flow rates increase.




*Retractable Spray Header  
with Removable Spray  
Nozzles*



Only two fasteners have to be removed to release each filter panel



This can be easily accomplished from the walkway



The filter basin does not have to be drained prior to the removal of filter media panels


## SIMPLE MAINTENANCE

The backwash spray header is retractable for easy access from the walkway. Tools are not necessary for the inspection and replacement of nozzles.

Inspection and maintenance is simple because the filter discs operate partially submerged.

The Hydrotech Discfilter's filter panels are secured to the disc by a single end cap, allowing for easy inspection and replacement from the walkway. Simple and efficient, the panel's patented design facilitates replacement without the need for expensive service or system downtime.

If operational or performance needs change, the design allows for an easy switch to a filter media with a different opening size.



## PROCESS

The influent flows by gravity into the filter discs from the center drum. Solids are separated from the water by the filter media mounted on the two sides of the discs, which are partially submerged. With this arrangement, the solids are retained within the filter discs while only the clean water flows to the outside of the discs and into the collection tank. Maintenance is reduced since there is no accumulation of solids in the tank.

During normal operation, the discs remain static until the water level in the inlet channels rises to a specific point, which then automatically initiates the backwash cycle. The filtered effluent provides a perfect source of backwash water, eliminating the need for a separate source of cleaning water or an additional clean water collection tank.

Clean effluent is pumped to the backwash spray header and nozzles, washing solids into the collection trough as the discs rotate. The backwash water required is 1-3 percent of the total flow to the filter, depending on solids loading rates. Maximum allowable head loss in continuous operation is 12 inches.

## ADVANTAGES

- Meets or exceeds Title 22 requirement at various influent turbidity levels and hydraulic loading rates up to 6 gpm/ft<sup>2</sup>
- Consistently produces quality effluent despite high-solids loadings, upsets and backwash cycles
- Available with self-contained tankage
- Capable of installation in an existing basin
- Requires far less space than other filtration methods
- All units supplied with aluminum covers
- Simplified control system and less installation costs than other filtration technologies



I. Kruger Inc.  
401 Harrison Oaks Blvd.  
Suite 100  
Cary, NC 27513


Phone 919.677.8310  
Fax 919.677.0082  
Website [www.krugerusa.com](http://www.krugerusa.com)





Always one step ahead:  
**The 7 Series with the right drive  
for every application**


Geared motors



## We don't stop at just setting standards


The geared motors from SEW-EURODRIVE bear a distinctive wave design on the housing. This design not only gives the motors a unique appearance easily recognized, it also characterizes the unit's hidden strengths. The results speak for themselves: leading edge technology, high impact load capacities, top power density and a wide variety of designs to suit every application.

Torque and permissible overhung loads are impressively high in relation to the structural volume of the motor. This level of performance has been made possible by the compact and extremely rigid housing with its low weight and optimum magnetic flux. The sealing surfaces are not subject to any load pressure as the force flows through the one-piece housing. For maximum safety during use, all the shaft-keyway joints in the geared motors are positive connections. Precision positioning tasks are taken care of by the helical, parallel and helical-bevel geared motors, also available in reduced backlash design.




The 7 Series incorporates power and variety in a scope offered only by SEW-EURODRIVE

The optimized magnetic flux ensures that forces are not applied to the sealing surfaces and effectively prevents leakage



Driving the world: with innovative drive solutions for all branches of industry and for every application. Products and systems from SEW-EURODRIVE for any application, worldwide! SEW-EURODRIVE products can be found in a variety of industries, e.g. automotive, building materials, food and beverage as well as metal-processing. The decision to use drive technology "made by SEW-EURODRIVE" stands for safety regarding functionality and investment.





## Helping you set your own priorities


You can best decide how you want to set up your system to suit your needs – the millions of combinations made possible by the modular system gives you the freedom to do just that, even as far as the type of fixture for assembly and integration into the system are concerned. Even with adapters for IEC and NEMA-compliant motors or standard market servomotors, the SEW-EURODRIVE solution fits best.

Unique not only as far as the range of sizes and gear ratios is concerned, our geared motors have even more to offer: exemplary reliability, overload capacity and long service life, the results of our proficiency in serial production. Our benchmarking criteria and quality control system eliminate every weak link in the production chain. Every component must meet the highest requirements.

**Reliability and environmental friendliness** are the result of our high-quality sealing concept and housing design. The use of oil seals and resilient sealing surface gaskets in combination with the favorable magnetic flux prevents leakages and prolongs maintenance-free service life. The units are also exceptionally quiet. This is achieved by precision gearing, particularly torsionally rigid housing and by the wave design that absorbs sound waves and significantly reduces noise levels.




The capabilities of the geared motors illustrates clearly why SEW-EURODRIVE is represented by its drive technology in the most important branches the world over. Power density, design diversity, overload capacity and reliability give the user the security desired – optimally positioned and highly efficient in every application.



## The helical geared motors for complete satisfaction

Six single-stage and thirteen multi-stage geared motors covering a power range of 70 to 18.000 Nm maintain optimum equilibrium between power and space requirements. The tried and proven modular system together with their stringent quality criteria make it possible for SEW-EURODRIVE to supply torques and gear ratios that are incomparably closely spaced and widely varied. This exceptional diversity of design sets new standards in this field of drive engineering.

### More efficiency in every situation




The variety of sizes allows all requirements to be met. For high output speeds, the RX57 to RX107 series of single-stage gear units offers compact solutions. And when weight-watching is an issue, we have something special to offer from our range of multi-stage gear units: The use of aluminum casting makes the R17 and R27 models particularly light – ideal for satellite drives and for use in light machine constructions.

Every design has efficient immersion lubrication and a breather valve which not only help assure performance reliability, but also secure other no less important benefits such as long service life and low maintenance requirements.

Whether with closely spaced torque steps and ratios or high output speeds – a helical geared motor fits in every situation

The complete program of helical geared motors provides the correct size and power for every application



R17

R27

R37

R47

R57

R67

R77

R87

R97


R107

## Helical geared motors

Type	Maximum torque [Nm]	Gear ratios	No. of ratios
RX57	70	1.30 – 5.50	14
RX67	135	1.40 – 6.07	13
RX77	215	1.42 – 8.00	16
RX87	405	1.39 – 8.65	16
RX97	595	1.42 – 8.23	15
RX107	830	1.44 – 6.63	13
R17	85	3.83 – 81.64	31
R27	130	3.37 – 135.09	35
R37*	200	3.41 – 134.82	35
R47*	300	3.83 – 176.88	43
R57*	450	4.39 – 186.89	37
R67*	600	4.29 – 199.81	36
R77*	820	5.31 – 195.24	32
R87*	1.550	5.30 – 246.54	35
R97*	3.000	4.50 – 289.74	36
R107*	4.300	4.92 – 251.15	34
R137*	8.000	5.15 – 222.60	30
R147*	13.000	5.00 – 163.31	25
R167*	18.000	10.24 – 229.71	28

Multi-stage gear units achieve gear ratios of up to  $i > 27.000$

\* Also available in low backlash design



R137


R147

R167

## Parallel shaft helical geared motors: the fitting solution for tight spaces

Where installation space is limited, the slim-lined parallel shaft helical geared motors cut a particularly good figure. The wide torque range providing torque from 130 to 18.000 Nm, and the many different sizes and designs means that even under the most unfavorable conditions, a wide variety of applications can be catered for.

### Drives for every branch



A standard drive that is not only favored because of its constructional properties. Typically found in conveyor and materials processing applications, the parallel shaft helical geared motors from SEW-EURODRIVE can always be relied on to solve a diversity of drive tasks.

Even under the most unfavorable conditions, parallel shaft helical geared motors always find their place

## Parallel shaft helical geared motors

Type	Max. torque [Nm]	Gear ratios	No. of ratios
F27	130	4.16 – 140.74	31
F37*	200	3.77 – 128.51	33
F47*	400	4.99 – 190.76	32
F57*	600	5.18 – 199.70	34
F67*	820	3.97 – 228.99	37
F77*	1.500	4.28 – 281.71	39
F87*	3.000	4.12 – 270.68	36
F97*	4.300	4.57 – 276.77	40
F107*	7.680	6.22 – 254.40	32
F127*	12.000	4.68 – 170.83	28
F157*	18.000	11.92 – 267.43	27

Multi-stage gear units make gear ratios up to  $i > 31.000$  possible

\* Also available in low backlash design

## Helical-bevel geared motors yield up to 50.000 Nm on a constant basis


The principle of compact design as applied to the generation of 7 Series units is most clearly represented by the helical-bevel gear unit. These units are sophisticated angular gear units for all mechanical engineering applications demanding space-saving installation. At the same time they also provide a powerful torque range extending from 200 to 50.000 Nm.

Helical-bevel gear units from SEW-EURODRIVE provide a high degree of efficiency of over 96 percent in both torque directions and at all input speeds. A performance designed to last – high-endurance gearing gives drives full-force torques while making them wear-free.

### Energy saving, low-maintenance

The remarkably high efficiency of our helical-bevel geared motors makes them into real energy-savers. The enduring maintenance-free service life is yet another rea-

son that you can use not only AC asynchronous motors but also asynchronous and synchronous servomotors for every occasion.



Compact and strong, these bundles of energy are a popular choice for every application because of their efficiency



## Helical-bevel geared motors


Type	Max. torque [Nm]	Gear ratios	No. of ratios
K37	200	5.36 – 106.38	25
K47	400	5.81 – 131.87	27
K57	600	6.57 – 145.14	27
K67	820	7.28 – 144.79	26
K77	1.550	7.24 – 192.18	29
K87	2.700	7.21 – 197.37	28
K97	4.300	8.71 – 176.05	25
K107	8.000	8.69 – 143.47	24
K127	13.000	8.68 – 146.07	21
K157	18.000	12.65 – 150.41	17
K167	32.000	17.34 – 164.50	15
K187	50.000	17.18 – 179.86	18

Ratios up to  $i > 32.000$  can be achieved with multi-stage gear units.  
All gear unit types are also available in low backlash design.

## Helical-worm geared motors – for thinking round corners

Due to their excellent economic efficiency, these drives can be used in every branch of industry – tailored individually to torque and speed requirements. The gear ratios afforded by the worm gear stage, and the low noise levels during operation make these geared motors ideal low-cost solutions for simple applications. And yet, they can deliver quite a powerful performance: the torque ranges from 92 to 4.000 Nm.

### Simple, practical and unobtrusive



Installment of angular gear units is particularly space-saving. The attenuation characteristics are a further bonus resulting from the simplicity of the mechanical design. As a result of the longitudinal application of the force on the input shaft, the torque impulses are dampened.

In spite of their strength, the noise level produced is very low, even for this type of gear unit. This means that our helical-worm geared motors can be used even for stage elevators.

Our helical-worm gear units fill even the smallest niches in drive engineering




## Helical-worm geared motors


Type	Max. torque [Nm]	Gear ratios	No. of ratios
S37	92	6.80 – 157.43	30
S47	170	7.28 – 201.00	31
S57	295	7.28 – 201.00	31
S67	520	7.56 – 217.41	33
S77	1.270	8.06 – 256.47	37
S87	2.280	7.88 – 288.00	36
S97	4.000	8.26 – 286.40	34

Multi-stage gear units make gear ratios of up to  $i > 33.000$  possible

## Flexibility even on the drive end



The input shaft assembly and different adapters are the best examples of how our gear units can increase efficiency everywhere and in every drive



**In line with its family of gear units,** SEW-EURODRIVE also provides optimum solutions for motorizing the drive end, increasing both flexibility and efficiency. Input covers and motor adapters are characterized by their compact dimensions, low weight and long service life. Tailored specifically to our gear units, these components ultimately increase the economic efficiency of the drive as a whole.

SEW-EURODRIVE offers eight different cover sizes for different tasks. Depending on the gear unit and drive tasks involved, these options optimize connection to the drive. Take for example height adjustment of cover's of which the motor mounting platform height adjustment simplifies assembly and startup. Or again, the integrated back stop ensuring compact drive design and optimum operation.

### **Adapters open up more possibilities**

In addition to the integrated torque limiting coupling, there are also a variety of adapters with integrated hydraulic centrifugal couplings. As a standard, the centrifugal coupling comes with protection against overheating and it can optionally be equipped with an integrated mechanical brake and/or integrated backstop. The AM adapter series means that all IEC motors in sizes 63 to 280 and all NEMA motors in sizes 56 to 365 can be fitted to the 7 Series gear units. The AQ adapter is for servomotors; these can be either servomotors with interlocking keyed connections (AQA) or non-positive connections with clamping ring hubs (AQH).


## Planetary geared motors for moving with the greatest precision, even in the largest applications

The compact, low backlash planetary gear units in both single-stage and multi-stage design can handle the most demanding positioning tasks – powerfully and with the utmost precision. The compact design of these units is particularly advantageous when it comes to cramped space conditions.


The highest quality in both production and assembly guarantee circumferential backlash of less than six angular minutes or less than three angular minutes in the reduced versions. Additional measures can even produce circumferential backlash of less

than one angular minute. This low backlash together with a wide variety of integer ratios delivers the highest possible precision in all positioning tasks.

The big jobs, such as typical heavy engineering tasks, are taken care of by our heavy duty industrial gear units. The helical gear, bevel gear, and planetary gear units reliably produce torque of more than 1.000.000 Nm.




The particularly compact planetary geared motors (left) or the particularly powerful planetary geared motors (right) – power and precision for every application.



## Quality, even in the lower ranks

The single-stage SPIROPLAN® right-angle geared motors deliver their power reliably and quietly: in a power range of up to 0.09 to 1.1 kW, the Spiroplan series delivers output torques of up to 70 Nm thanks to the particularly quiet, wear-free gearing. In combination with its compact design and light-weight aluminum housing, the unit is almost perfectly discreet.



The SPIROPLAN® angular geared motors round off the range and variety of our geared motors program to perfection

## Discover the endless possibilities – all you need is a PC


Even without detailed knowledge of our products, you can use the EKAT, our electronic catalog, to find the right drive quickly and simply. You only need to enter values such as power, torque, speed and gear unit type. The EKAT is a straight-forward PC application for Windows 95/98/NT4.0/2000.

The data of the complete gear unit program including planetary gear units with AC motors and drives with particularly low speed ranges are contained in EKAT. For quick and focused product selection, specification data input is supported by both graphics and texts. The selection of certain search options optimizes the display of all the relevant products.

By displaying the most important data in the selection list, it is possible to quickly compare the different products. For a better comparison of different drives, for instance the different kinds of gear unit types with the same motor, several selection lists can be displayed simultaneously beside each other.

## Put your unit exactly where you want it – our mounting positions make it possible

Once you have chosen the right type of unit for the job, you have to find the right mounting position. Our mounting positions make this an easy task: you just select the installment position for the gear unit from only six different mounting positions, M1 to M6. This simple principle is based on the standardization of the mounting positions for all the gear unit types and the reduction of the mounting position designations.





## Intelligent electronics to smarten up our drives

In the field of drive electronics we have the right solutions for every requirement and every task. Take, for instance, our frequency inverters: MOVITRAC® 31C for every application, with a power range of 0.55 to 55 kW, or MOVITRAC® 07, the compact frequency inverter, providing comprehensive functionality together with simple operation.

Our intelligent drive inverters, MOVIDRIVE® and MOVIDRIVE® *compact*, are equipped with the IPOS<sup>plus</sup> positioning and sequence control as a standard. This optional functionality allows even the most difficult drive tasks to be resolved economically and flexibly.

We have complete future-safe system solutions for decentralization purposes. MOVIMOT®, the geared motor with the integrated frequency inverter, and MOVI-SWITCH®, the geared motor with the integrated circuit breaker and protective function are the compact specialists for decentralized drive application. The custom-designed field distributors and cable systems round off our system to help you optimize the implementation of your decentralized systems and engineering concepts.

This program will always have the perfect solution for you:  
 MOVIMOT® (right)  
 MOVIDRIVE® and  
 MOVIDRIVE® *compact*  
 (below left)  
 or MOVITRAC®  
 (below right)





## How to drive the world

With people who think right faster and develop the future with you.

With drives and controls that automatically improve your work performance.

With comprehensive knowledge of the most important branches of industry today.

With uncompromising quality whose high standards will simplify daily operations.



With innovative ideas that offer a solution for tomorrow's problems today.

With a service network that is always close at hand around the world.

With a global presence for quick and convincing solutions. Anywhere.

With an Internet presence that is available around the clock and offers information as well as software updates.

**SEW-EURODRIVE**  
Driving the world

## SEW-EURODRIVE is right there for you:

**Argentina**  
Tel. (0 33 27) 45 72 84  
Fax (0 33 27) 45 72 21

**Australia**  
Tel. (03) 99 33 10 00  
Fax (03) 99 33 10 03

**Austria**  
Tel. (01) 6 17 55 00-0  
Fax (01) 6 17 55 00-30

**Belgium**  
Tel. (0 10) 23 13 11  
Fax (0 10) 23 13 36

**Brazil**  
Tel. (0 11) 64 60-64 33  
Fax (0 11) 64 80-46 12

**Canada**  
Tel. (9 05) 7 91-15 53  
Fax (9 05) 7 91-29 99

**Chile**  
Tel. (02) 6 23 82 03  
6 23 81 63  
Fax (02) 6 23 81 79

**China**  
Tel. (0 22) 25 32 26 12  
Fax (0 22) 25 32 26 11

**Colombia**  
Tel. (05 71) 5 47 50 50  
Fax (05 71) 5 47 50 44

**Czech Republic**  
Tel. 02/20 12 12 34/35/36  
Fax 02/20 12 12 37

**Denmark**  
Tel. 4395 8500  
Fax 4395 8509

**Finland**  
Tel. (3) 58 93 00  
Fax (3) 7 80 62 11

**France**  
Tel. 03 88 73 67 00  
Fax 03 88 73 66 00

**Great Britain**  
Tel. 19 24 89 38 55  
Fax 19 24 89 37 02

**Hong Kong**  
Tel. 2-7 96-04 77  
Fax 2-7 95-91 29

**Hungary**  
Tel. (01) 2 02 74 84  
Fax (01) 2 01 48 98

**India**  
Tel. (02 65) 83 10 86  
Fax (02 65) 83 10 87

**Italy**  
Tel. 02-9 69 80-1  
Fax 02-96 79 97 81

**Japan**  
Tel. (0 53 83) 7 38 11-13  
Fax (0 53 83) 7 38 14

**Malaysia**  
Tel. (07) 3 54 57 07  
3 54 94 09  
Fax (07) 3 54 14 04

**Mexico**  
Tel. (5) 8 88-18 16 + 18 31  
Fax (5) 8 88-20 06

**Netherlands**  
Tel. (0 10) 4 46 37 00  
Fax (0 10) 4 15 55 52

**New Zealand**  
Tel. (09) 2 74 56 27  
2 74 00 77  
Fax (09) 2 74 01 65

**Norway**  
Tel. (69) 24 10 20  
Fax (69) 24 10 40

**Peru**  
Tel. (5 11) 349-52 80  
Fax (5 11) 349-30 02

**Poland**  
Tel. (0 42) 6 16 22 00  
Fax (0 42) 6 16 22 10

**Portugal**  
Tel. (02 31) 20 96 70  
Fax (02 31) 20 36 85

**Russia**  
Tel. (8 12) 3 26 09 41  
5 35 04 30  
Fax (8 12) 5 35 22 87

**Singapore**  
Tel. 86 21 701-705  
Fax 8 61 28 27

**South Africa**  
Tel. (0 11) 4 94 43 80  
Fax (0 11) 4 94 23 00

**South Korea**  
Tel. (0 31) 4 92-80 51  
Fax (0 31) 4 92-80 56

**Spain**  
Tel. 9 44 31 84 70  
Fax 9 44 31 84 71

**Sweden**  
Tel. (0 36) 34 42 00  
Fax (0 36) 34 42 80

**Switzerland**  
Tel. (0 61) 4 17 17 17  
Fax (0 61) 4 17 17 00

**Thailand**  
Tel. (0 38) 21 45 29 / 30  
Fax (0 38) 21 45 31

**Turkey**  
Tel. (2 16) 4 41 91 63  
Fax (2 16) 3 05 58 67

**USA**  
Tel. (8 64) 4 39-87 92  
75 37  
Fax (8 64) 9 49 30 39

**Venezuela**  
Tel. (0 41) 32 95 83  
Fax (0 41) 38 62 75

**SEW  
EURODRIVE**

SEW-EURODRIVE GmbH & Co  
P.O.Box 30 23 · D-76642 Bruchsal/Germany  
Phone +49-7251-75-0 · Fax +49-7251-75-1970

→ [www.sew-eurodrive.com](http://www.sew-eurodrive.com)



# Commercial & Industrial Products



GRUNDFOS




# CR

*Vertical, multi-stage, centrifugal pumps for a wide range of applications*

## Features Benefits

- Configured for a broad range of high-pressure applications, Grundfos CR pumps offer a space-saving, vertical in-line design that provides easy installation for both new and retrofit systems. Competitively priced, CR pumps feature corrosion-resistant stainless steel or titanium construction for extended reliability and performance. High efficiency design helps reduce operating costs and minimizes downtime for maintenance and repairs.
- All 60 HZ Grundfos CR pumps are direct-coupled to a standard NEMA-C Face motor for rigidity. 50 HZ motors are IEC for convenient local service. Self-adjusting mechanical shaft seals offer maintenance-free reliability and are rated to 250°F and 435 PSI for standard models and to 355°F with the optional *Cool Top™*. Impellers, chambers, shaft and guide vanes are fabricated of stainless steel or titanium for quiet and efficient long-term operations.



### **CR 32, 45, 64, & 90**

#### **Pump Bearing Plate**

Optional plate allows use of a standard motor bearing.

#### **Motor Coupling**

Ample spacing between motor and pump shaft allows for a seal change without removing the motor (15-60 HP only).

#### **Cartridge Shaft Seal**

Pump disassembly not required to change the seal.

#### **Split-Pump-Head**

Provides greater flexibility plus a cast stainless pump head option for aggressive fluids.

#### **O-Ring Sleeve Sealing**

Prevents sleeve joint leaks even during wide temperature swings.

#### **Highly Efficient Hydraulic Design**

Chamber and impeller design, coupled with laser welding, provide efficiencies greater than 80%.

#### **Wear Resistant Bearings**

Heavy duty intermediate (Graflon® or Bronze) and bottom bearing (Tungsten carbide).

#### **Flexible Connections**

Universal flange system—flexible and easy to install.


**Common Applications:** *Dead-end water supply for fire protection*

- *Water Treatment: RO, DI and Filtration* • *Oil Refining: Steam* • *Electronic Manufacturing*  
• *Parts Washers* • *Lumber and Mining* • *Chemical: Refinery and Offshore*



## Special Construction


In CRN units, the pumped fluid comes in contact only with stainless steel components. The 316 stainless steel makes these upgraded units ideal for pumping deionized water and light chemicals.



CRN


CRNG

## Service Kits and Tools




"The STACK<sup>®</sup>" allows fast, on-site pump repairs. This pre-assembled, ready-to-install rebuild kit includes the pump shaft, impellers, chambers and all associated hardware.

Add your choice of many seal kit configurations and you have a "new pump."



## CR-90

Maximum 60 HP,  
630 GPM,  
80%+ efficiency



## Titanium too

Grundfos CR models are now available up to 115 GPM for salt water, chloride based fluids, and other fluids which require titanium for long life. Ask for the CRT2, CRT4, CRT8, and CRT 16.

## Operating Specs

Fluid Temp: 5° to 250°F – optional to 355°F

Flow Range: 1.2 to 630 GPM


Head Range: 0 to 1,005 ft.

Max. Working Press.: 360/435 PSI –  
optional to 653 PSI

Max. Ambient Temp: 104°F –  
higher when the motor is derated

HP Range: 1/2 to 60 HP

## CR Performance Range



GRUNDFOS



# CHI/CHIE/CH/CHN

*Multi-purpose, stainless steel pumps for commercial/industrial applications*

## Features Benefits

### CHI/CHIE/CH/CHN

- TEFC Motor
- UL Approved to US and Canadian Standards
- Bellows Type Shaft Seals
- Dual and Tri-Voltage Motors
- NPT Connection

### CHI


- All Liquid-Exposed Components Constructed of 316 Stainless Steel

### CHN


- All Liquid-Exposed Components Constructed of 304 Stainless Steel

### CH

- All Liquid-Exposed Components Constructed of 304 Stainless Steel and Cast Iron Suction and Discharge





**CHI**




**CHIE** provides all the benefits of the CHI, plus a fully integrated variable speed motor (1 x 230 volts), set-point potentiometer, and PI controller.

Also available, the CHIE-Plus™ includes all of the above, plus a pressure transducer, expansion chamber, and gauge; a complete system.




**CHN**


## Service Kits and Tools




Seal kits, separate motors and pump components are readily available for service or repair.



**CH**




**Common Applications:** D. I. Water • Hot and Cold Liquids • Oils  
• Mild Acids • Aromatic Hydrocarbons • Potable Water • Alkalis



### CH Model Range

Models	Flow Range (GPM)	Suction	Discharge	HP Range
CH2	1.3 - 18	1" NPT	1" NPT	1/2 - 1-1/2
CH4	2.2 - 40	1-1/4" NPT	1" NPT	3/4 - 1
CH8	3.5 - 53	1-1/2" NPT	1-1/4" NPT	1 - 2
CH12	5.2 - 70	1-1/2" NPT	1-1/2" NPT	2


### CH Performance Range



### CHI Model Range

Models	Flow Range (GPM)	Suction and Discharge	HP Range
CHI2	1.2 - 20	1" NPT	1/3 - 1
CHI4	3.0 - 40	1-1/4" NPT	1/3 - 1-1/2
CHI8	4.0 - 55	1-1/2" NPT	3/4 - 1-1/2
CHI12	6.0 - 70	1-1/2" NPT	1/2 - 2

### CHI Performance Range\*



\*CHIE does not cover all CHI models.

**GRUNDFOS**



# E-pump™

*Grundfos pumps powered by the new, variable frequency drive (VFD) MLE motors.*

## Features Benefits

- E-pump products are new from Grundfos, combining state-of-the-art frequency converter technology with the well-known range of Grundfos pumps for building, industrial, irrigation, and municipal applications.
- E-pump models are available in single or three-phase. Single-phase Grundfos MLE motors with a built-in PI controller and connections for external control signals are available in sizes of 1/3 - 1-1/2 HP.
- The new three-phase MLE motor offers motor sizes of 1 - 10 HP. In addition to a built-in PI controller, connections for external signals, and set-point selection, this motor can also communicate with the Grundfos remote control unit, the R100. The R100 offers a number of additional control features, data collection, and print functions with an optional hand-held printer.
- E-pump models are available with or without a factory installed pressure sensor.




### *Common Applications:*

*Industrial • Commercial • Irrigation • Municipal*

# CRE-Plus™


Single pump, CRE system, "plug-n-play"



## CRE-Plus


CRE-Plus provides all system components in a "plug-n-play" package. Systems are available in single and three phase.

### CRE-Plus Performance Range



## The All-In-One E-pump... The Optimum Answer

*Compared to a set-up consisting of a separate pump, frequency converter and sensor, E-pump products provide a number of clear advantages:*



### Easy installation:

An E-pump is just as easy to install as a standard pump. Once connected to the mains, the pump is ready for operation. All internal connections and settings are made at the Grundfos factory.




### Cost effective:

Variable speed pumps use less energy, reduce pump wear, and do not require periodic adjustments.



### Every component from the same supplier:

With pumps, frequency converters and sensors from one supplier, sizing, selection and ordering could not be simpler. The Grundfos service department offers total product service.



### Flexible:

An E-pump is so flexible that it is possible to adapt it to any application. Just a few types replace many standard pumps. E-pump products are ideal when pumps need replacing.

GRUNDFOS





# BoosterpaQ®

*Compact, high-pressure booster systems for universal, broad applications.*

## Features Benefits

- The pumps are the rugged Grundfos type CR multi-stage centrifugal pumps. They guarantee reliable and trouble-free operation with optimum efficiency, compactness and easy service. Grundfos MLE motors with built-in frequency converters are just one of the unique optional features of the BoosterpaQ system.
- The advanced controller with simple operation is characteristic of the BoosterpaQ range. The controller can switch the system on/off or regulate the frequency of up to six parallel connected pumps to maintain constant pressure regulation. As a result, your system will operate efficiently over wide flow ranges.
- BoosterpaQ systems are compact. The pumps are fitted with intake and discharge manifolds, including all necessary shut-off and non-return valves. Pressure transmitters ensure instant regulation. The 304 stainless steel frame and 316 stainless steel manifolds, apart from being corrosion-free, ensure water quality and cleanliness. Minimum pressure loss is assured by specially designed non-return valves.

## Operating Specs

Fluid Temp: 5° to 176°F – optional higher rating

Max. Flow: 3,800 GPM



Head Range: 0 to 500 ft.

Max. Working Press.: 250 PSI – additionally limited by the tank rating

Max. Ambient Temp: 104°F – higher when motors are derated

HP Range: 1 to 50 HP – system total 300 HP, 6 pumps


## BoosterpaQ Performance Range



**Common Applications:** Commercial Buildings • Industrial Plants  
• Landscaping • Municipal • Agricultural

# SPK/CRK/MTR/MTC/MTA


Compact, multi-stage and single stage, centrifugal, immersible pumps for tank mounting




## Features Benefits

- Compact in size, Grundfos immersible multi-stage centrifugal pumps are engineered for various liquid handling applications. Typical applications include machine tool coolants, EDM, industrial parts washers and boiler condensate. Applicable liquids include hot and cold water, mixtures of water and water soluble cooling and cutting oils, and other thin, clean, non-aggressive and non-explosive liquids.
- Featuring maintenance-free mechanical seals, they are self-priming, self-venting and are designed to operate at pressures up to 350 PSI and temperature extremes of 15° - 210°F. A positive priming screw eliminates dry running. The unique suction strainer can be removed for easy maintenance.
- The highly efficient design of the Grundfos immersible pumps features stainless steel construction for vital components, assures corrosion-free reliability and saves energy costs.
- The Grundfos SPK, CRK and MTR pumps are direct-coupled and available with either NEMA-C Face or IEC and 50 HZ or 60 HZ motors. The MTC extended shaft motor design eliminates the need for a coupling, resulting in a very low profile design for restricted height applications. Grundfos immersible pumps are designed to be mounted vertically.


**SPK Performance Range**




**MTA Performance Range**



**MTC Performance Range**



**MTR/CRK Performance Range**




- Models MTC 8, 12, and 16, featuring the same design and features as MTC2 and MTC4, were recently added to extend the performance range.
- Another new addition, the MTA pump provides a performance range which fits lathes, grinders, small mills, and other applications.
- Grundfos coolant pumps SPK, CRK, and MTR are available with the Grundfos MLE, variable speed motor. Variable speed pumps provide the right flow and pressure, save energy, and when demand varies, they often eliminate the requirement for multiple pumps.

**Common Applications:** Machine Tool Coolant • Parts Washing  
• Filtration • Transfer and Drainage • Pressure Boosting •  
Deionized Water • Hot/Cold Washdown


# BM

Sealless, multi-stage pumps for high-pressure application

**BM 4"**



**BM 8"**



**BMQ & BMQE-NE**



## Features Benefits

- Stainless steel booster sleeve provides for an extremely quiet and safe-to-operate module
- Radial bearings are lubricated by the pumped liquid, requiring no additional lubrication or maintenance
- No-seals to leak or replace.
- Standard materials are 316 stainless steel for the pump and motor. Some motors are 904L and pump ends are available in 904L upon request. 304 stainless steel construction is available for less demanding applications.

**NEW! Constant Pressure/Variable Speed.**

### Operating Specs

Max. Fluid Temp: 104°F – optional higher temperatures for 6" (140°F) and 8" (194°F) motors

Max. Flow: BM 1,100 GPM; BMQ 42 GPM


Max. Developed Head: BM 1,600 ft.; BMQ 700 ft.

Max. Working Press.: 1,100 PSI (4" & 6"), 1,015 PSI (8")


HP Range: BM 5 to 125 HP – optional to 200 HP; BMQ 1.5 HP

50 HZ or 60 HZ

### BM Performance Range (60 HZ shown)



### BMQ Performance Range



**Common Applications:** Ultra Filtration • Reverse Osmosis •  
Pressure Boosting • Wash-Down • Circulation



# Quick Application Guide

	Series CR, CRE & CRE-Plus Pumps	Series SPK/CRK/ MTR/MTC/MTA Pumps	Series HS Pumps <small>(END SUCTION NOT SHOWN)</small>	BoosterpaQ <sup>®</sup>	Series CH/CHN/CHI Pumps	Series BM & BMQ Pumps
Aqua Farming						
Boiler Feed		< 194°F				
Chilled Water						
Circulation						
Condensate Transfer						
Cooling Towers						
Cooling Units						
Deaerators						
Deionized Water					CHI only	
De-Watering						
Dosing Systems						
Drainage						
Effluent						
Filter Systems						
Filtration						
Fountains						
Glycol Solutions						
Graywater						
HVAC						
Industrial						
Irrigation						
Liquid Transfer						
Machine Tool Coolants						
Marine Service					CHI only	
Municipal Water Supplies						
Paint Booth						
Parts Washing						
Pressure Boosting						
Process Water						
Quench Water						
Reverse Osmosis						
Sump						
Swimming Pools (Commercial)						
Ultra Filtration						
Washdown						
Water Treatment						
<b>Specifications</b>						
Capacity in U.S. GPM	1.2 - 630	1.2 - 450	0 - 175	0 - 3800	1.2 - 70	0 - 1500
Total Head in Feet	0 - 1005	0 - 970	0 - 160	0 - 500	0 - 265	0 - 1600
HP	1/2 - 60	1/2 - 40	1/3 - 7-1/2	1.0 - 300 *****	1/3 - 2	1 - 250
Temperature Range (°F)	-40° - 355°	14° - 210°	180° *	5° - 176° ***	**	0° - 104° ***
Max. Working Pressure	435 PSI ***	435 PSI	125 PSI	250 PSI ****	145 PSI	1160 PSI

\*For continuous duty, 211°F for intermittent duty      \*\*5°F to 230°F for CHI, 32°F to 194°F for CH

\*\*\*Higher upon request


\*\*\*\*Limited by the selected tank

\*\*\*\*\*Total system HP, 6 pumps


GRUNDFOS



# Other Grundfos Products




**HVAC Products**




**SSE Products**

**Environmental Products**



**Groundwater Products**




VISIT US ON THE WEB AT  
**www.us.grundfos.com**



Ask us about our  
"CI" CD Rom, which  
includes WinCAPS®  
pump sizing and  
selection software  
program, technical  
specifications, and  
other new information.



## GRUNDFOS



*Leaders in Pump Technology*



**Grundfos Pumps Corporation**

3131 N. Business Park Avenue, Fresno, CA 93727  
(559) 292-8000 FAX (559) 291-1357

**Customer Service Centers**

Allentown, PA • Fresno, CA  
(800) 333-1366 FAX (800) 333-1363

ISO 9001



**Grundfos Canada, Inc.**

2941 Brighton Rd.  
Oakville, Ontario L6H 6C9, Canada  
(905) 829-9533 FAX (905) 829-9512



**Bombas Grundfos de Mexico, S.A. de C.V.**

Boulevard TLC #15  
Parque Industrial Silva Aeropuerto  
C.P. 66600, Apodaca, N.L. Mexico  
52-8-144-4000 FAX 52-8-144-4010

Available from:

Performance curves and technical information listed as a range only and subject to change without notice. Consult a Grundfos product submittal data sheet for exact pump specifications.

L-CI-SL-001 Rev. 8/00  
PRINTED IN USA

## LIMITED WARRANTY

Products manufactured by GRUNDFOS PUMPS CORPORATION (Grundfos) are warranted to the original user only to be free of defects in material and workmanship for a period of 18 months from date of installation, but not more than 24 months from date of manufacture. Grundfos' liability under this warranty shall be limited to repairing or replacing at Grundfos' option, without charge, F.O.B. Grundfos' factory or authorized service station, any product of Grundfos manufacture. Grundfos will not be liable for any costs of removal, installation, transportation, or any other charges which may arise in connection with a warranty claim. Products which are sold but not manufactured by Grundfos are subject to the warranty provided by the manufacturer of said products and not by Grundfos' warranty. Grundfos will not be liable for damage or wear to products caused by abnormal operating conditions, accident, abuse, misuse, unauthorized alteration or repair, or if the product was not installed in accordance with Grundfos' printed installation and operating instructions.

To obtain service under this warranty, the defective product must be returned to the distributor or dealer of Grundfos products from which it was purchased together with proof of purchase and installation date, failure date, and supporting installation data. Unless otherwise provided, the distributor or dealer will contact the Grundfos factory or authorized service station for instructions. Any defective product to be returned to the factory or service station must be sent freight prepaid, documentation supporting the warranty claim and/or a Return Material Authorization must be included if so instructed.

GRUNDFOS WILL NOT BE LIABLE FOR ANY INCIDENTAL OR CONSEQUENTIAL DAMAGES, LOSSES, OR EXPENSES ARISING FROM INSTALLATION USE OR ANY OTHER CAUSES. THERE ARE NO EXPRESS OR IMPLIED WARRANTIES, INCLUDING MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE, WHICH EXTEND BEYOND THOSE WARRANTIES DESCRIBED OR REFERRED TO ABOVE.

Some jurisdictions do not allow the exclusion or limitation of incidental or consequential damages and some jurisdictions do not allow limitations on how long implied warranties may last. Therefore, the above limitations or exclusions may not apply to you. This warranty gives you specific legal rights and you may also have other rights which vary from jurisdiction to jurisdiction.



Grundfos Pumps Corporation • 3131 N. Business Park Avenue • Fresno, CA 93727  
Customer Service Centers: Allentown, PA • Fresno, CA  
Phone: (559) 292-8000 • Fax: (559) 291-1357  
Canada: Oakville, Ontario • Mexico: Apodaca, N.L.

Visit our website at [www.us.grundfos.com](http://www.us.grundfos.com)

L-SPK-TL-003 | Rev. 401  
PRINTED IN USA

# SPK/CRK/MTR COOLANT PUMPS

## Installation and Operating Instructions

### CONTENTS

#### SAFETY WARNING

Page 1

#### PRE-INSTALLATION CHECKLIST INSTALLATION PROCEDURES

Pages 1-2

#### OPERATING THE PUMP

Page 3-4

#### MOTORS


Page 5

#### TROUBLESHOOTING

Page 6-7

#### LIMITED WARRANTY

Page 10



Please leave these instructions with the pump for future reference



# SAFETY WARNING

## Shock Hazard

A faulty motor or wiring can cause electrical shock that could be fatal, whether touched directly or conducted through standing water. For this reason, proper grounding of the motor frame to the power supply's grounding terminal is required for safe installation and operation.

In all installations, the above-ground metal plumbing should be connected to the power supply ground as described in Article 250-80 of the National Electrical Code.

## Electrical Work

All electrical work should be performed by a qualified electrician in accordance with the latest edition of the National Electrical Code, local codes and regulations.

### WARNING:

The safe operation of this pump requires that it be grounded in accordance with the National Electrical Code and local governing codes or regulations. Connect the ground wire to the grounding screw in the terminal box and then to the acceptable grounding point.

## Pre-Installation Checklist

### 1. Confirm You Have The Right Pump

- Read the nameplate to ensure it is the one you ordered
- Compare the pump's nameplate data or its performance curve (for head, GPM, etc.) with the application in which you plan to install it.
- Will it do what you expect it to do?

#### 1.1 Pump Key for SPK/CRK

Pump Range	GRK	4	180	2	-X	-X	-XXXX
Nominal Flow Rate in gpm							
Number of Stages x 10 (SPK x 1)							
Number of Impellers							
Code for Pump Version							
Code for Pipework Connection							
Code for Materials							
Code for Shaft Seal and Rubber Pump Parts							

#### 1.2 Pump Key for MTR

Pump Range	MTR	32	-2	1	-1	-X	-X	-XXXX
Nominal Flow Rate in m³/h								
Number of Stages								
Number of Impellers (if only used if less than 1000 gpm)								
Number of Impellers with reduced diameter								
Code for Pump Version								
Code for Pipework Connection								
Code for Materials								
Code for Shaft Seal								

#### Code for Pump Version

U = Standard pump  
U = BEHA pump

#### Physical Changes

B = Oversized motor  
P = Intermediate (1 flange size smaller)  
T = Oversized motor (2 flange sizes larger)  
X = Special product

#### Code for Pipe Work Connection

G = ANSI flange  
J = JIS flange  
W = Internal thread

#### Code for Materials

K = Stainless steel  
I = Nonstainless parts converted to SS  
K = Intermediate bearings are bronze  
X = Special product  
D = Gland bearing

#### U - G - A - R - B - E

#### Type of Shaft Seal

A = Rubber seal with fixed seal driver  
B = Rubber bellows seal  
C = O-ring seal with a spring working as a driver  
R = Cartridge with reduced diameter stationary ring  
H = Balanced seal, cartridge  
E = O-ring seal, cartridge

#### Materials of Secondary Seal and other Parts

G = Cast iron  
B = Cast iron  
V = FKM  
K = Kalrez  
X = Special product

#### Materials of Stationary Ring

B = Carbon, plastic impregnated  
C = Other types of carbon  
U = Tungsten carbide  
Q = Silicon carbide  
I = Impregnated silicon carbide  
H = Carbon with impregnated Tungsten Carbide (Hybrid)

#### Material of Rotating Ring

B = Carbon, plastic impregnated  
C = Other types of carbon  
U = Tungsten carbide  
Q = Silicon carbide  
I = Impregnated silicon carbide  
H = Carbon with impregnated Tungsten Carbide (Hybrid)

### 2. Check the Condition of The Pump

The shipping carton your pump came in is specially designed around your pump during production to prevent damage. As a precaution, it should remain in the carton until you are ready to install it. At that point, look at the pump and examine it for any damage that may have occurred during shipping. Examine any other parts of the shipment as well (electrical control boxes, etc.) for any visible damage. If you find any, contact the transportation company in writing and ask to have it inspected.

### 3. Electrical Requirements

#### Supply Power

The incoming electrical supply should be verified so the voltage, phase and frequency match that of the pump motor. The proper operating voltage and other electrical information can be found on the motor nameplate. These motors are designed to run on  $\pm 10\%$  of the nameplate-rated voltage. For dual-voltage motors, the motor should be internally connected to operate on the voltage closest to the 10% rating. I.e., a 208 voltage motor wired per the 208 volt connection diagram. Wiring connection diagrams can be found on the plates attached to the motor.

If voltage variations are larger than  $\pm 10\%$ , do not operate the pump.

#### Field Wiring

Wire sizes should be based on the current carrying properties of a conductor as required by the latest edition of the National Electrical Code or local regulations. Direct on line (D.O.L.) starting is approved due to the extremely fast run-up time of the motor and the low moment of inertia of pump and motor. If D.O.L. starting is not acceptable and reduced starting current is required, an auto transformer or resistor starter should be used. It is suggested that a fused disconnect be used for each pump where service and standby pumps are installed.

#### Motor Protection

##### 1. Single-Phase Motors:

With the exception of 7 1/2 and 10 HP motors (which require external protection) single-phase SPK/CRK pumps are equipped with multi-voltage, squirrel-cage induction motors with built-in thermal protection.

## Installation Procedures

2. **Three-Phase Motors:** SPK/CRK/MTR pumps with three-phase motors must be used with the proper size and type of motor-starter to ensure the motor is protected against damage from low voltage, phase failure, current imbalance and overloads. A properly sized starter with manual reset and ambient-compensated extra quick trip in all three legs should be used. The overload should be sized and adjusted to the full-load current rating of the motor. Under no circumstances should the overloads be set to a higher value than the full load current shown on the motor nameplate. This will void the warranty.

Overloads for auto transformers and resistor starters should be sized in accordance with the recommendations of the manufacturer.

### 4. Glance Through This Guide


Even if you are very familiar with the installation of this pump, a quick glance through the remaining sections of this guide may help you avoid a potential problem.

## Installation Procedures

### Installing The Pump

#### Pump Location

Grundfos SPK/CRK/MTR pumps are designed for tank-mounting and may be installed in either a vertical or horizontal orientation. Where the unit is to be installed so as to position its mounting flange below the liquid level or in a pressurized tank, a gasket must be fitted between the pump's mounting flange and tank.



Pump Model	QA	QB	QC	Discharge	Mounting Hole Dia.
SPK12/48 (NEMA)	5.5" (140)	5.3" (135)	7.1" (180)	1 1/2" NPT	0.28" (7)
SPK12/48 (IEC)	3.9" (100)	4.5" (115)	5.1" (130)	3/4" BSP	0.28" (7)
SPK12/48 (IEC)	5.5" (140)	5.3" (135)	7.1" (180)	1 1/2" BSP	0.28" (7)
CRK2/4 (NEMA)	5.5" (140)	5.3" (135)	7.1" (180)	1 1/2" NPT	0.37" (9.5)
CRK2/4 (IEC)	5.5" (140)	5.3" (135)	7.1" (180)	1 1/2" BSP	0.37" (9.5)
CRK16 (NEMA)	7.5" (200)	6.9" (225)	9.9" (250)	2.0" NPT	0.35" (9)
MTR32	7.5" (200)	6.9" (225)	9.9" (250)	2 1/2" ANSI	0.47" (12)
MTR45/64	9.5" (240)	10.5" (265)	11.4" (290)	2 1/2" ANSI	0.47" (12)

#### Pipework




The discharge ports of SPK/CRK pump units which are supplied for use with NEMA motors have 1 1/2 inch female NPT threads. Other discharge pipe sizes must be accommodated via the use of appropriate adapter bushings.

#### Suction Conditions

The bottom of the pump strainer must be at least 1.0 inch above the bottom of the tank. The pumps are designed to provide full performance down to a level of A mm above the bottom of the strainer.


At a liquid level between A and B mm above the bottom of the strainer, the built-in priming screw will protect the pump against dry running.

MTR32, 45 and 64 pumps have no priming screw.



PUMP TYPE	A (IN.)	B (IN.)
CRK2/4	1 1/2"	1 1/4"
CRK16	2 0"	1 0"
SPK12/48	1 1/2"	1 0"
MTR32/45/64	2 1/4"	-

In general, it is recommended that the pump strainer be located as near as possible to the bottom of the tank. This maximizes first-stage submergence in condensate transfer applications and maintains fluid velocities in cutting lubricant applications (see Figure 4).



#### Separation of Particles

Out of consideration for the pump, the distribution system, the cutting tools and the treated materials, cooling/cutting fluids should, wherever possible, be free of particles before entering the pump unit. The system's requirements as to the purity of the pumped fluid depend on the machining methods, the treated materials and other criteria. Filtration methods should be matched to these requirements. Larger particles are unable to enter the pump with the pumped fluid due to the effect of the built-in filter screen; particles Ø2 mm or smaller are allowed to enter the SPK and CRK pumps, and particles Ø4 mm or smaller are allowed to enter the MTR pump.

#### Bypass

A bypass line or pressure relief valve should be installed in the discharge pipe if there is any possibility the pump may operate against a closed valve in the discharge line (or in any other no-flow condition). Flow through the pump is required to ensure adequate cooling and lubrication of the pump is maintained. The following table shows minimum flow rates:

PUMP TYPE	MINIMUM FLOW RATE
SPK1	1.0 GPM
SPK2	1.2 GPM
SPK4	3.0 GPM
SPK8	5.3 GPM
CRK2	1.2 GPM
CRK4	3.0 GPM
CRK8	5.3 GPM
CRK16	8.5 GPM
MTR 32	15 GPM up to 76°F (80°C)
	35 GPM 76° - 194°F (80-70°C)
MTR45	20 GPM up to 76°F (80°C)
	44 GPM 76° - 194°F
MTR64	28 GPM up to 76°F (80°C)
	55 GPM 76°F - 194°F (80°C - 80°C)


## Operating The Pump

- Check to see that the gaps between the coupling halves are equal. Loosen and re-adjust if necessary.
- Be certain the pump shaft can be rotated by hand. If the shaft cannot be rotated or it binds, disassemble and check for misalignment.
- Replace the two coupling guard screens.

### Starting The Pump The First Time

- Air Elimination**  
As long as the pump body is partially submerged in fluid, the pump may be started against an open or a closed discharge line. If the discharge line is open, the air will quickly escape through the discharge pipe. If the discharge line is closed, the air will be pressed down through the pump body and out into the tank so that the discharge pressure will quickly reach its maximum (shutoff) level.

If the pump is fitted with a vent valve, this valve must be opened while running the pump against a closed valve. Once a steady stream of liquid is running out of this vent valve it can be closed.



### Check the Direction of Rotation

- Switch the **POWER OFF**.  
a. Make sure the pump has been filled and vented.  
b. Remove the coupling guard and rotate the pump shaft to be certain it turns freely. Replace the coupling guard.  
c. Verify that the electrical connections are in accordance with the wiring diagram on the motor.  
d. Switch the power on and observe the direction of rotation. When viewed from the top, the pump should rotate counter-clockwise.  
e. To reverse the direction of rotation, first switch OFF the supply power.  
f. On three-phase motors, switch any two power leads at the load side of the starter. On single-phase motors, refer to the connection diagram on the nameplate.  
g. Change wiring as required.  
h. Switch the power ON and check for proper motor rotation.

### Starting And Adjusting

Before starting the pump, make sure that:

- The pump body is partially submerged in the fluid.
- The direction of rotation is counter-clockwise when viewed from the top.
- All piping connections are light and the pipes are adequately supported.
- The pump inlet screen is clean and unblocked.
- Depending on the application, it may be necessary to start the pump against a closed discharge valve in order to prevent system damage due to water hammer. If so, this valve should be opened in a gradual manner after the pump is started. Unless used as a flow throttling device, make sure this valve is completely opened.
- Check and record the voltage and amperage of the motor. Adjust the motor overloads if required.
- Check and record operating pressures if pressure gauges have been installed.

## Operating the Pump

### Replacing The Motor

If the motor is damaged due to bearing failure, burning or electrical failure, the following instructions detail how to remove the motor for replacement. It must be emphasized that motors used on SPK/CRK/MTR pumps are specifically selected to our rigid specifications. Replacement motors must be of the same frame size.

#### Removing the Old Motor

- Remove the coupling guard screens.
- Using the proper metric allen wrench, loosen the four cap screws in the coupling.
- With the correct size wrench, loosen and remove the four bolts which hold the motor to the discharge section of the pump end.
- Lift the motor straight up until the shaft is free from the coupling.

#### Installing the New Motor

- Thoroughly clean the surfaces of the motor and pump end mounting flanges. Set the motor on the pump end.
- Place the terminal box in the desired position by rotating the motor.
- Insert the mounting bolts, then tighten diagonally and evenly.
- Using a larger screwdriver, raise the pump shaft by placing the tip of the screwdriver under the coupling and carefully elevating the coupling to its highest point. Note: The shaft can only be raised approximately 0.20 inches (5 mm).
- Now lower the shaft halfway back down the distance you just raised it (approximately the thickness of a dime), and retighten the metric cap screws in the coupling. Be sure to tighten the top and bottom screws on one side of the coupling and then the other. Torque the coupling screws to the following specifications.

Coupling Bolt Size	Minimum Torque
M6	10 lbf-ft
M8	23 lbf-ft
M10	46 lbf-ft

# Operating The Pump

Do not over grease the bearings. Over greasing will cause increased bearing heat and can result in bearing/motor failure.

## Periodic Safety Checks

At regular intervals depending on the conditions and time of operation, the following checks should be made:

1. Pump meets required performance and is operating smoothly and quietly.
2. There are no leaks, particularly at the shaft seal.
3. The motor is not overheating.
4. Remove and clean all strainers or filters in the system.
5. Verify the tripping of the motor overload protection.
6. Check the operation of all controls. Check unit control cycling twice and adjust if necessary.
7. If the pump is not operated for unusually long periods, the unit should be maintained in accordance with these instructions. In addition, if the pump is not drained, the pump shaft should be manually rotated or run for short periods of time at monthly intervals.

If the pump fails to operate or there is a loss of performance, refer to the Troubleshooting section on page 6.

8. Check all controls for proper operation. If pump is controlled by a pressure switch, check and adjust the cut-in and cut-out pressures. If low-water-level controls are used, be sure the low-level switch is properly adjusted so the pump cannot run if the pump should break suction.

## Improper Operation

**No Flow**  
Under no circumstances should the pump be operated for any prolonged periods of time without flow through the pump. This can result in motor and pump damage due to overheating. A properly sized relief valve should be installed to allow sufficient water to circulate through the pump to provide adequate cooling and lubrication of the pump bearings and seals.

## Pump Cycling

Pump cycling should be checked to ensure the pump is not starting more than:

- 20 times per hour on 1/2 to 5 HP models
- 15 times per hour on 7 1/2 to 15 HP models
- 10 times per hour on 20 to 40 HP models

Rapid cycling is a major cause of premature motor failure due to increased heat buildup in the motor. If necessary, adjust controls to reduce the frequency of starts and stops.

## Maintenance

Grundfos SPK/CRK/MTR multi-stage centrifugal pumps installed in accordance with these instructions and sized for correct performance will operate efficiently and provide years of service. The pumps are water-lubricated and do not require any external lubrication or inspection. The motors will require periodic lubrication as noted in the following paragraphs.

## Motor Lubrication

Electric motors are pre-lubricated at the factory and do not require additional lubrication at start-up. Motors containing sealed bearings do not require additional lubrication during the first 15,000 hours of operation. Motors with grease fittings should only be lubricated with a lithium based grease.

Severity of Service	Ambient Temperature (Maximum)	Atmospheric Contamination	Approved Types of Grease
Standard	104°F (40°C)	Clean, little corrosion	Shell Doliun R Or compatible
Severe	122°F (50°C)	Moderate dirt, corrosion	Chevron SRI#2
Extreme	> 122°F (50°C) or Class H insulation	Severe dirt, abrasive dust, corrosion	type of grease

## Lubrication Schedule

NEMA/IEC Frame Size	Standard Service Interval	Severe Service Interval	Extreme Service Interval	Weight of Grease to Add Oz./Gross	Volume of Grease to Add In/(Teaspoons)
Up through 210 (132)	5500 hrs.	3600 hrs.	2750 hrs.	0.30 (8.4)	0.6 (2)
Over 210 through 280 (180)	3600 hrs.	2200 hrs.	1800 hrs.	0.61 (17.4)	1.2 (3.9)
Over 280 up through 360 (225)	2200 hrs.	1100 hrs.	900 hrs.	0.81 (23.1)	1.6 (5.2)
Over 360 (225)	1100 hrs.	550 hrs.	450 hrs.	2.12 (60.0)	4.1 (13.4)

\*The grease outlet plug MUST be removed before adding new grease.

# Motors

\* The information below was updated March 30, 2001, but is subject to change without notice. Grundfos makes no claims or warranties regarding the accuracy of the information herein.

## Totally Enclosed Fan Cooled (TEFC) Baldor Motors\* 60 HZ - Two Pole (3450 RPM)

HP	PH	SERVICE FRAME	NEMA	VOLTS	FULL LOAD	LOCKED ROTOR	S.F.	EFF.	POWER FACTOR	LINE TO LINE RESISTANCE AT 25 DEG C	INS. CLASS	GRUNDFOS PART NO.
1/3	1	55C	55C	115/230	2	24.5/12.3	7.5/3.8	88	88	6.489/7.172	B	K 85.60001
1/2	1	55C	55C	208/230/460	15.1/7.7	38.1/18.8	70.0	85	85	38.2/42.3	B	K 85.60001
1/2	1	55C	55C	115/230/230	14.3/7.7	38.1/18.8	70.0	85	85	38.2/42.3	B	K 85.60001
3/4	1	55C	55C	115/230/230	9.9/5.4	13.7/7.7	85.0	85	85	34.0/37.84	B	K 85.60002
3/4	1	55C	55C	208/230/460	2.7/2.4	33.0/15	11.4/5.7	85.0	74	2.32/2.578	B	K 85.60003
1	1	55C	55C	208/230/460	11/5.5	77/38.5	14.4/7.2	86.0	81	2.34/2.58	B	K 85.60004
1	1	55C	55C	208/230/460	11/5.5	77/38.5	14.4/7.2	86.0	81	2.34/2.58	B	K 85.60004
1 1/2	1	55C	55C	208/230/460	17/9.5/4.8	79/43.5/23.9	20.4/11.3/10.3	71.0	79	1.178/1.302	B	K 85.60005
2	1	55C	55C	208/230/460	23/11.5	118.4/79.3	25.4/12.7	74.0	82	0.9/1.2	F	K 85.60006
2	1	55C	55C	208/230/460	16.5/4.2	38.7/35.1	6.3/4.3	76.5	93	0.7/1.1	B	K 85.60006
3	1	55C	55C	208/230/460	30/16.5/11	172/95.1/48	32.7/16.1	77.0	87	0.5/0.9	F	K 85.60007
3	1	55C	55C	208/230/460	7.8/7.0/3.7	59.7/54.2/27	---	82.5	87	5.5/6.1	F	K 85.60008
3	1	55C	55C	208/230/460	29/16.1/14.5	170/93.5/48	32.8/16.1/14.5	75.0	88	5.88/6.89	F	K 85.60008
3	1	55C	55C	208/230/460	8.2/7.8/3.9	77.4/72.5	8.2/7.8	85.0	89	0.3/0.5	F	K 85.60009
5	1	55C	55C	208/230/460	13.2/12.6	103.9/44.7	15.1/3.6/8	85.5	93	2.5/4.9	F	K 85.60010
7 1/2	1	55C	55C	208/230/460	94/33.1	240/417	38.3/35.5	82.0	91	2.16/2.531	F	K 85.60017
10	1	55C	55C	208/230/460	13.2/12.6	103.9/44.7	15.1/3.6/8	85.5	93	2.5/4.9	F	K 85.60017
10	1	55C	55C	208/230/460	25/47.2	232.2/103.9	28.3/27.1/13.8	85.5	91	1.92/1.8	F	K 85.60022
10	1	55C	55C	208/230/460	25/47.2	232.2/103.9	28.3/27.1/13.8	85.5	91	1.92/1.8	F	K 85.60022
25	3	55C	55C	208/230/460	46/23	402/210	62.4/26.2	88.5	92	0.38	F	K 85.60026
25	3	55C	55C	208/230/460	61/58/29	482.1/58/29	70.4/29.3	91.0	89	30/33	F	K 85.60026
30	3	55C	55C	208/230/460	72/38	444/222	80/40	88.5	89	0.319	F	K 85.60027
40	3	55C	55C	208/230/460	84/47	580/290	105.2/52.5	93.2	88	0.178	F	K 85.60027

\*\*\* Information unavailable at time of update.

## Open Drip Proof (ODP) Baldor Motors\* 60 HZ - Two Pole (3450 RPM)

HP	PH	SERVICE FRAME	NEMA	VOLTS	FULL LOAD	LOCKED ROTOR	S.F.	EFF.	POWER FACTOR	LINE TO LINE RESISTANCE AT 25 DEG C	INS. CLASS	GRUNDFOS PART NO.
1/3	1	55C	55C	115/230	2	24.5/12.3	7.5/3.8	88	88	6.489/7.172	B	K 84.20002
1/2	1	55C	55C	208/230/460	15.1/7.7	38.1/18.8	70.0	85	85	38.2/42.3	B	K 84.20002
1/2	1	55C	55C	115/230/230	14.3/7.7	38.1/18.8	70.0	85	85	38.2/42.3	B	K 84.20002
3/4	1	55C	55C	115/230/230	9.9/5.4	13.7/7.7	85.0	85	85	34.0/37.84	B	K 84.20002
3/4	1	55C	55C	208/230/460	2.7/2.4	33.0/15	11.4/5.7	85.0	74	2.32/2.578	B	K 84.20002
1	1	55C	55C	208/230/460	11/5.5	77/38.5	14.4/7.2	86.0	81	2.34/2.58	B	K 84.20002
1	1	55C	55C	208/230/460	11/5.5	77/38.5	14.4/7.2	86.0	81	2.34/2.58	B	K 84.20002
1 1/2	1	55C	55C	208/230/460	17/9.5/4.8	79/43.5/23.9	20.4/11.3/10.3	71.0	79	1.178/1.302	B	K 84.20002
2	1	55C	55C	208/230/460	23/11.5	118.4/79.3	25.4/12.7	74.0	82	0.9/1.2	F	K 84.20002
2	1	55C	55C	208/230/460	16.5/4.2	38.7/35.1	6.3/4.3	76.5	93	0.7/1.1	B	K 84.20002
3	1	55C	55C	208/230/460	30/16.5/11	172/95.1/48	32.7/16.1	77.0	87	0.5/0.9	F	K 84.20002
3	1	55C	55C	208/230/460	7.8/7.0/3.7	59.7/54.2/27	---	82.5	87	5.5/6.1	F	K 84.20002
3	1	55C	55C	208/230/460	29/16.1/14.5	170/93.5/48	32.8/16.1/14.5	75.0	88	5.88/6.89	F	K 84.20002
3	1	55C	55C	208/230/460	8.2/7.8/3.9	77.4/72.5	8.2/7.8	85.0	89	0.3/0.5	F	K 84.20002
5	1	55C	55C	208/230/460	13.2/12.6	103.9/44.7	15.1/3.6/8	85.5	93	2.5/4.9	F	K 84.20002
7 1/2	1	55C	55C	208/230/460	94/33.1	240/417	38.3/35.5	82.0	91	2.16/2.531	F	K 84.20002
10	1	55C	55C	208/230/460	13.2/12.6	103.9/44.7	15.1/3.6/8	85.5	93	2.5/4.9	F	K 84.20002
10	1	55C	55C	208/230/460	25/47.2	232.2/103.9	28.3/27.1/13.8	85.5	91	1.92/1.8	F	K 84.20002
10	1	55C	55C	208/230/460	25/47.2	232.2/103.9	28.3/27.1/13.8	85.5	91	1.92/1.8	F	K 84.20002
25	3	55C	55C	208/230/460	46/23	402/210	62.4/26.2	88.5	92	0.38	F	K 84.20002
25	3	55C	55C	208/230/460	61/58/29	482.1/58/29	70.4/29.3	91.0	89	30/33	F	K 84.20002
30	3	55C	55C	208/230/460	72/38	444/222	80/40	88.5	89	0.319	F	K 84.20002
40	3	55C	55C	208/230/460	84/47	580/290	105.2/52.5	93.2	88	0.178	F	K 84.20002

\*\*\* Information unavailable at time of update.


## IEC IP55, IM 3611 (V18)\* 60 HZ - Two Pole (3450 RPM)

Kw	HP	PH	S.E.	VOLTS	FULL LOAD	LOCKED ROTOR	S.F.	EFF.	POWER FACTOR	LINE TO LINE RESISTANCE AT 25 DEG C	INS. CLASS	GRUNDFOS PART NO.
0.37	1/2	3	1.0	220-230/460	1.1/0.6/0.34	6.1/2.1/1.3	5.4	87	87	0.86/0.7	B	K 84.20002
0.55	3/4	3	1.0	220-230/460	1.5/0.8/0.4	8.3/4.4/2.6	5.4	87	87	0.86/0.7	B	K 84.20002
0.75	1	3	1.0	220-230/460	2.1/1.2/0.6	12.5/6.6/3.8	5.4	87	87	0.86/0.7	B	K 84.20002
1.1	1 1/2	3	1.0	220-230/460	2.8/1.6/0.8	17.0/9.5/5.4	5.4	87	87	0.86/0.7	B	K 84.20002
1.5	2	3	1.0	220-230/460	3.5/2.0/1.0	22.0/12.5/7.0	5.4	87	87	0.86/0.7	B	K 84.20002
2.2	3	1.0	1.0	220-230/460	4.5/2.6/1.3	29.0/16.5/9.5	5.4	87	87	0.86/0.7	B	K 84.20002
3	4	1.0	1.0	220-230/460	5.5/3.2/1.6	35.0/20.0/11.0	5.4	87	87	0.86/0.7	B	K 84.20002
4	5.5	3	1.0	220-230/460	6.5/3.8/1.9	42.0/24.0/13.0	5.4	87	87	0.86/0.7	B	K 84.20002
5.5	7 1/2	3	1.0	220-230/460	7.5/4.4/2.2	49.0/28.0/16.0	5.4	87	87	0.86/0.7	B	K 84.20002
7.5	10	3	1.0	220-230/460	9.0/5.2/2.6	58.0/33.0/19.0	5.4	87	87	0.86/0.7	B	K 84.20002
11	15	3	1.0	220-230/460	11.0/6.3/3.1	70.0/40.0/23.0	5.4	87	87	0.86/0.7	B	K 84.20002

# Troubleshooting

## Preliminary Checks

### Supply Voltage



#### How to Measure

Use a volt meter, (set to the proper scale) measure the voltage at the pump terminal box or starter.

On single-phase units, measure between power leads L1 and L2 (or L1 and N for 115 volt units). On three-phase units, measure between:

- Power leads L1 and L2
- Power leads L2 and L3
- Power leads L3 and L1

#### What it Means

When the motor is under load, the voltage should be within  $\pm 10\%$  of the nameplate voltage. Larger voltage variation may cause winding damage and indicate a poor electrical supply. The pump should not be operated until these variations have been corrected.

If the voltage constantly remains high or low, the motor should be changed to the correct supply voltage.

### Current Measurement



#### How to Measure

Use an ammeter, (set on the proper scale) to measure the current on each power lead at the terminal box or starter.

Current should be measured when the pump is operating at constant discharge pressure.

#### What it Means

If the amp draw exceeds the listed service factor amps (SFA) or if the current imbalance is greater than 5% between each leg on three-phase units, check the following:

1. Burned contacts on motor starter.
2. Loose terminals in starter/terminal box or possible wire defect.
3. Too high or too low supply voltage.
4. Motor windings are shorted or grounded. Check winding and insulation resistances.
5. Pump is damaged causing a motor overload.


### Lead-To-Ground Resistance



#### How to Measure

Turn off power and disconnect the supply power leads in the pump terminal box. Using an ohmmeter, set the scale selector to R x 100 and zero adjust the meter by touching the two ohmmeter leads together. Touch one ohmmeter lead to a motor lead and one to ground. Repeat for each lead. If measured resistance does not exceed 1,000,000 ohms, motor is bad and in need of replacement.

### Winding Resistance



#### How to Measure — NEMA

Turn off power and disconnect the supply power leads in the pump terminal box. Using an ohmmeter, set the scale selector to R x 1 and zero adjust the meter by touching the two ohmmeter leads together.

Touch the leads of the ohmmeter to two motor leads.


Single phase motors - touching the leads of the ohmmeter to the two outgoing "hot" motor leads (either a single motor lead or combination of leads joined together) will measure the main winding's resistance.

Three phase motors - touching the leads of the ohmmeter to any two hot leads will measure that winding's resistance. Repeat for all three possible lead combinations (L1 and L2, L2 and L3, L1 and L3)

#### How to Measure — IEC

Turn off power and disconnect the supply power leads in the pump terminal box. Using an ohmmeter, set the scale selector to R x 1 and zero adjust the meter by touching the two ohmmeter leads together.

Touch the leads of the ohmmeter to two motor terminals as follows:



#### What it Means

If all ohm values are normal, the motor windings are neither shorted nor open. If any one ohm value is less than normal ( $\sim 25\%$ ), that motor winding may be starting to short. If any one ohm value is greater than normal ( $\sim 25\%$ ), the winding may be starting to open. If some values are high and some are low, the leads may be connected incorrectly, or they may have a break in the insulating jacket.

## Diagnosing Specific Problems

The following checklist should help you troubleshoot most of the problems you may encounter during installation.

If The Pump...	It May Be Caused By...	Check This By...	Correct It By...
Does Not Run	No power at pump panel	Check for voltage at panel	If no voltage at pump panel, check feeder panel for tripped circuits
	Fuses are blown or circuit breakers are tripped	Turn off power and remove fuses. Check for continuity with ohmmeter	Replace blown fuses or reset circuit breaker. If new fuses blow immediately, the electrical installation, motor and wires must be checked.
	Motor starter overloads are burned or have tripped out	Check for voltage on line and load side of starter	Replace burned starters or reset. Inspect starter for other problems.
	Starter does not energize	Energize control circuit and check for voltage at the holding coil	If no voltage, check control circuit fuses. If voltage, check holding coil for shorts. Replace bad coil.
	Defective controls	Check all safety and pressure switches for operation. Inspect contacts in control devices	Replace worn or defective parts or controls
	Motor is defective	Turn off power and disconnect wiring. Measure the lead to lead resistance with ohmmeter (RX-1). Measure lead to ground (values with ohmmeter (RX-100K). Record measured values	If an open or grounded winding is found, remove motor and repair or replace
	Defective capacitor. (Single-phase motors)	Turn off power and discharge capacitor. Check with ohmmeter (RX-100K).	
	Pump is bound	Turn off power and manually rotate pump shaft	
Pump Runs But At Reduced Capacity or Does Not Deliver Water	Wrong rotation	Check wiring for proper connections	When the meter is connected to the capacitor, the needle should jump toward 0 ohms and slowly drift back to infinity ( $\infty$ ). Replace if defective
	Pump body not partially submerged	Turn pump off, close isolation valve(s). Check fluid level	If shaft does not rotate easily, check coupling setting and adjust as necessary. If shaft rotation is still tight, remove pump and inspect. Disassemble and repair
	Strainers, inlet screen or valves are clogged	Remove strainer, screen or valve and inspect	Correct wiring
	Entrained air in pumpage	Check tank conditions for cascading fluid or vortexing	Provide submergence by increasing fluid level in tank or sump; alternatively by repositioning pump at lower level
	Fluid cavitation	Compare pump NPSH requirements to available NPSH at pump flow rate	Clean and replace strainer, screen and/or valves
	Pump worn	Install pressure gauge, start pump, gradually close the discharge valve and read pressure at shutoff	Install baffle(s) in tank. Relocate inlet pipe. Decrease pump flow rate
	Pump impeller or guide vane is damaged	Disassemble and inspect pump passageways	Decrease pump flow rate and/or fluid temperature. Increase first-stage submergence
Fuses Blow or Motor Overload Relay Trips	Low voltage	Check voltage at starter panel and motor	Convert measured pressure (in PSI) to head (in feet): Measured PSI x 2.31 (GPM) = _____ (feet) Refer to the specific pump curve for additional information. If the pump head is less than curve, pump is probably OK. If not, remove pump and inspect
	Motor overloads are set too low	Cycle pump and measure amperage	Remove any foreign materials found
	Three-phase current is imbalanced	Check current draw on each lead to the motor	If voltage varies more than $\pm 10\%$ , contact power company. Check wire sizing
	Motor is shorted or grounded	Turn off power and disconnect wiring. Measure the lead-to-lead resistance with an ohmmeter (RX-1). Measure lead-to-ground values with an ohmmeter (RX-100K) or a megohm meter. Record values	Increase heater size or adjust trip setting to a maximum of motor nameplate (full load) current
	Wiring or connections are faulty	Check proper wiring and loose terminals	Must be within $\pm 5\%$ . If not, check motor and wiring. Raising all leads may eliminate this problem
	Pump is bound	Turn off power and manually rotate pump shaft	If an open or grounded winding is found, remove the motor, repair and/or replace
	Defective capacitor. (Single-phase motors)	Turn off power and discharge capacitor. Check with ohmmeter (RX-100K)	Tighten loose terminals. Replace damaged wire
	Motor overloads at higher than ambient temperature than motor	Use a thermometer to check the ambient temperature near the overloads and motor. Record these values	If shaft does not rotate easily, check coupling setting and adjust as necessary. If shaft rotation is still tight, remove pump and inspect. Disassemble and repair

## Notes

## Notes



## D. INSTALLATIONS OF LIKE PROJECTS



# Hydrotech Filtration Reference List

Please note: the information contained in this document is CONFIDENTIAL. This should not be reproduced, distributed, etc. without the express written consent of Kruger, Inc.

Project Name	Address	Contact	Phone	Engineer	Contractor	Flowrate (MGD)	Application	Installed/Startup
Moncks Corner (Bard), SC		Louis Mintz	843-761-8300	RMT, Inc.	Owner's Contractor	0.46	latex facility (industrial WWTP)	2005
Hastings WWTP, FL		Joey Lundquist	904-692-1520	Mittauer & Associates	Mack Concrete Industries	0.60	Tertiary filtration, chlorine disinfection	2002
Baldwin CDBG WWTP, FL	800 Main Street Baldwin, FL 32234	Don Casey	904-266-9055	Mittauer & Associates	Meadors Construction Co., Inc.	0.80	Tertiary filtration/Reuse	2004
Eagle Ridge, FL		Tony Wierzbicki	407-869-1919	CPH Engineers, Inc.	Utilities, Inc. of Eagle Ridge	1.00	Tertiary filtration	2005
Carey Station, GA	4310 North Carey Station Road Greensboro, GA 30642	Bob Sheldon	888-429-3794	HSF Engineering, Inc.	Southern Champion Construction, Inc.	1.25	Tertiary filtration/Reuse	2004
Oconee Crossings WTP - Greensboro, GA		Bob Sheldon	888-429-3794	HSF Engineering, Inc.	Southern Champion Construction, Inc.	1.25	Tertiary filtration/Reuse, UV disinfection	2002
Palatka WWTP	3010 Brown's Landing Road Palatka, FL 32177	Drew Platt	386-329-0146	Hartman & Associates	Meadors Construction Co., Inc.	1.75	Tertiary Filtration	2004
Village of Marissa WTP - Marissa, IL		William Yates	618-295-2018	Unavailable	Unavailable	3.73	Tertiary filtration, no disinfection	2002
Marburg (Winder), GA		Leslie Harbin	770-867-4334	HSF Engineering, Inc.	Southern Champion Construction, Inc.	3.75	Tertiary Filtration	2005
City of Mesquite, NV		Bill Tanner	702-346-5237	Stantec Consulting	Owner's Contractor	4.00	Tertiary filtration, UV disinfection	2002
Alamogordo WWTP, NM		Cheryl Richardson	505-439-1606	USFilter Engineering & Construction	USFilter Engineering & Construction	4.00	Tertiary filtration/reuse	2002
N.E. Brunswick County, NC		Michael Painter	910-279-5249	W.K. Dickson & Co., Inc.	T.A. Loving	4.13	Tertiary filtration	2003

E. MANUFACTURER'S REPRESENTATIVE INFO

STEVE GARNICK

MISCO WATER

[sgarnick@miscowater.com](mailto:sgarnick@miscowater.com)

5976 W. Las Positas Blvd. #226

Pleasanton, CA 94588

Phone: 925-225-1900

Fax: 925-225-9200

## F. CONSTRUCTION METHODS

### 3 DELIVERY AND INSTALLATION

#### 3.1 Delivery

Krüger will coordinate shipping of the Discfilter to the job site. Prior to arrival, the contractor should review the submittal information for the weight of each Discfilter and verify adequate equipment capacity is available for unloading. Upon arrival, inspect each unit for damage due to shipping. Notify the Krüger Project Manager immediately of any damage noted.

For safe transport it is sometimes necessary to deliver some parts unmounted. Spare parts will typically be shipped attached or inside the equipment. Be sure to check all parts against the packing list. Handle fragile parts (such as filter panels) with care to avoid damage.


#### 3.2 Storage

If it is necessary to store the equipment for periods longer than a few days prior to installation, then certain precautions should be taken to prevent unnecessary damage:


- Preferably, the units should be stored inside with temperature above freezing.
- The filter media must be protected from direct sunlight and UV exposure. The covers for the unit must be kept in place during storage. For -2F type units, the filter media are exposed below the top of the frame. Protective wrapping or tarping must be kept in place to prevent exposure to sunlight.
- Spare filter panels must be stored to prevent exposure to sunlight due to the potential for deterioration. Spare panels should also be stored to prevent puncturing.

#### 3.3 Lifting

- Discfilters with tank (type 1F) may be lifted by a forklift or by using a crane and straps. See Figure 3.1 for lifting locations if using straps. Discfilters without tank (type -2F) may be lifted with a crane and straps. See Figure 3.2 for lifting locations.
- Note that lifting eyes have an approximate 1-1/2" to 2" diameter hole.




**Figure 3.1.**  
**Lifting points, Type 1F**



**Figure 3.2.**  
**Lifting Points, Type 2F**

### 3.4 Foundation

- Filter must be mounted on even surface with appropriate torsional and structural strength.
- The filter must be properly leveled in both directions (See Figure 3.3).
- Foundation/anchor bolts are required. The filter should be set in place to use as a template for anchor installation.
- A minimum of 24" (600mm) should be available around the filter to allow for maintenance. Elevated walkways are recommended in order to easily access the backwash header and filter media for service. However, walkways should NOT be attached or supported by the discfilter!



**Figure 3.3. Filter installation**

### **3.5 Installation**

- The filter should only be installed if the equipment is not damaged from transport or storage and all preparatory work is completed.
- Electrical specifications of the equipment must correspond to the available line current specifications.
- It is necessary to protect the filter from direct sunlight with outdoor installations as the heat and UV-radiation may otherwise destroy the filter elements.
- Upon placement, place a tarp or other cover over each unit until surrounding concrete work is complete. This is to protect from splashed concrete, dirt, or other materials.
- Protect the filter from freezing. At water temperatures of +5 °C (41 °F) and an air temperature warmer than -10 °C (14 °F), the lids and unit cover will be sufficient to protect it from freezing. At lower water and air temperatures, install the filter indoors.

### **3.6 Emergency by-pass**

Type 1F (with tank) Discfilters have a built-in emergency by-pass weir as standard. The bypassed water mixes with the filtered effluent, but avoids overflow of the unit during upset conditions (e.g. a power failure, excess flow, or excess solids loading). It is advantageous to have a separate by-pass chamber and flange provided with the unit to avoid excessive water level pressure over the filter cloth. A separate by-pass also provides the benefit of preventing untreated water from entering the filtered water basin/tank. For high-flow rate designs an external means of bypass may also be required.

For a type 2F Discfilter (without tank), the inlet box may be used as the emergency by-pass means. The bypassed water mixes with the filtered effluent, but avoids overflow of the unit during upset conditions. In the case of type 2F units, it is advantageous to have an external by-pass arranged to avoid excessive water level pressure over the filter cloth and prevent untreated water from entering the filtered water basin/tank.

Reference the drawings provided in Section 3 of the O&M Manual along with site construction drawings to determine whether a separate/external bypass is included in the design.

### **3.7 Drum and Backwash pump motor rotation**

A gear motor with a belt drive rotates the Discfilter for the 2200 model. Rotation speed can be altered using the frequency converter (VFD) installed in the control cabinet. Direction of rotation is marked on the motor cover. Verify proper motor rotation. Proper rotation for the Backwash Pump motor must also be verified.

### **3.8 Disc and Inlet drum assembly positioning**

The filter unit may be exposed to shock during transportation and/or installation. The drum level should be inspected and verified after completed installation. Contact Kruger personnel immediately if there is any evidence of misalignment.

### **3.9 Electrical**

Electrical connection shall be performed according to local regulations. Check the settings of motor protectors against amperage readings on the motors. Note that it is critical that the level sensor have an adequate ground for proper operation. If the level sensor is not operating properly, it may be necessary to verify that the grounding point for the sensor is adequate.

### **3.10 Pipe connections**

Nominal pipe sizes are indicated in the Technical specifications at Section 1 of the O&M Manual. Inlet water velocity should not exceed 1 m/s (3.28 ft/s) to avoid turbulence inside the drum unit.

Piping from the backwash sludge connection must have an inclination of at least 1% to avoid solids settling in the piping.

### **3.11 Backwash system**

The backwash pump will be delivered to the site separately from the Discfilter. Install the pump in the location as shown on the drawings. Mounting holes and supports are supplied on the unit for the pump to be bolted and connected. The pump will then require connection to the piping.

Any particles in the backwash water supply area (the filtered water tank/basin) must be removed in order to prevent clogging of the backwash nozzles or damage to the pump and/or filter media. Be certain that any debris or particles are cleaned from the tank/basin prior to filling with water. A simple in-line strainer is typically provided in the backwash piping in order to remove particles from the backwash system.



# **DISCFILTER PROCESS**

## **CONTRACTOR BRIEFING FOLDER**

# **Contractor Briefing Folder**

## **Table of Contents**

- 1. Purpose**
- 2. Kruger Responsibilities:**
  - a. Scope of Supply**
  - b. Shipping**
  - c. Installation Instructions**
  - d. Installation Checkout Services**
  - e. Start-up Checkout Services**
- 3. Contractor Responsibilities:**
  - a. Receiving of Equipment**
  - b. Storage of Equipment**
  - c. Equipment Installation**
  - d. Requests for Inspection Services**
  - e. Contractor Checklists**
- 4. Start-up Planning**
- 5. Contact Information**
- 6. Requests for Additional Services**
- 7. Checklist Forms**

## **1. Purpose**

The purpose of this document is to provide an overview of Kruger's scope of supply and services for this project and to summarize the responsibilities of both the Contractor and Kruger in the prosecution of the work.

It has been Kruger's experience that many of the problems experienced during project execution can be minimized when the Contractor's personnel are fully aware of the scope of work Kruger is contracted to supply and what the Contractor's obligations are pertaining to Kruger's involvement in the project.

This briefing folder has been prepared with a focus on those areas that have sometimes caused difficulties in earlier projects. Our intent in providing this document is to alert all parties to the project elements and communication that will facilitate efficient construction and successful project completion.

## **2. Kruger Responsibilities**

This section of the briefing folder provides a statement of Kruger's scope of supply for this project. In addition to the equipment we are providing, this section also provides a summary of our installation inspection and start-up services for this project.

### **2 a. Scope of Supply**

Kruger is responsible for the supply of equipment and services as detailed in the Engineer's contract specifications to the extent included in our Contract Agreement with the Contractor or Owner. Installation of the Kruger supplied equipment is the responsibility of the Contractor.

### **2 b. Shipping**

Most of the material for this project will be drop shipped from a Kruger authorized supplier and delivered directly to the site. The authorized supplier has been informed to follow the following instructions:

- All items delivered will be clearly identified with Kruger's name, Kruger's project name, Kruger's project number and the Contractor's/Owner's purchase order/contract number to Kruger
- All shipments will have a clear Packing List identifying all parts in the shipment. There should not be any Packing List with " 1 lot Machine Parts". The Packing List description will be descriptive.
- All boxes will be identified with a Packing List clearly identifying all the contents of each box.
- All equipment will be tagged with the corresponding tag numbers shown on the design drawings ( if applicable ).
- The shipper is required to call the jobsite 48 hours in advance of delivery, and make arrangements with the contractor for delivery of the shipment.

If there are more stringent requirements in the contract documents then they will take precedence over the above. If any of these requirements are not being followed, please notify the Kruger Project Manager immediately. The project manager will work with our suppliers to ensure the problem does not continue.

## **2 c. Installation Instructions**

Kruger will supply specific Installation Manuals for equipment manufactured by Kruger. These manuals will be provided to the Contractor prior to delivery of the equipment. For equipment **not** manufactured by **Kruger**, refer to appropriate section in the Installation, Operation and Maintenance Manual to determine the manufacturer's installation requirements.

## **2 d. Installation Inspection Services**

When the Contractor has completed installation of all the Kruger supplied equipment for this project, Kruger will schedule qualified field service personnel to review the installation upon receipt of the completed Contractor Pre-operational Checkout Checklist (Form CPO – 4). This checklist is included under Tab 7 of this briefing folder.

When the Pre-Operational Checkout of the equipment has been completed by the Kruger field service personnel, and the Contractor has sent a completed Contractor Functional (Process) Start-Up Checklist (Form CFS – 4), Kruger will schedule the appropriate field service personnel to conduct the Functional (Process) Start-Up Checkout. The Contractor Functional (Process) Start-Up Checklist is included under Tab 7 of this briefing folder.

## **2 e. Start-up Services**

Kruger's Functional (Process) Start-Up services include making final preparations for equipment operation and includes process optimization service to achieve specified effluent limits from the Kruger systems.

### 3. Contractor Responsibilities

This section of the briefing folder provides a summary of the Contractor's scope of work for this project pertaining to the Kruger supplied equipment.

#### 3 a. Receiving of Equipment

The Contractor is responsible for receiving and unloading of Kruger supplied equipment at the jobsite or designated delivery address. Kruger will instruct the trucking companies to comply with site delivery constraints and notices required by our agreement with the Contractor or Owner. Upon delivery to the site, the shipment should be inspected for missing parts and damage sustained in transit. Damaged and/or missing parts are to be noted and reported to the carrier and the Kruger Project Manager. The Contractor is responsible for promptly notifying the Kruger Project Manager within 2 working days if any of our shipments are received in damaged condition or are missing parts. This procedure will protect all parties until the responsibility for the damages or shortages is determined. Copies of delivery tickets must be mailed or faxed to the Kruger Project Manager upon receipt of our equipment at the jobsite.

#### 3 b. Storage of Equipment

The Contractor is responsible for storage and protection of Kruger supplied equipment upon delivery to the jobsite. Once the equipment has been checked for damages and/or shortages, use the following guidelines if it is intended to store the equipment.

Preferably all equipment should be warehoused to protect the equipment against inclement weather, dirt, physical damage and theft. **Spare parts should also be warehoused until turned over to the plant personnel.** When indoor storage is not available then outdoor storage is acceptable. In either case the following procedure should be followed:

- All equipment should be stored in a clean and dry area that provides adequate ventilation. All equipment must be stored with adequate support underneath to prevent distortion and to avoid any undesirable ground or floor conditions. Any tenting or tarpaulins must be well supported so to provide adequate ventilation.
- Recoat any parts with paint, primer or grease, which has been scratched or wiped clean of their protective coating during shipment or delivery. Periodic checking is necessary to remove any accumulated condensation or rust and to recoat as necessary.

- Mechanical equipment with rotating components i.e. motors, gear drives, etc. shall have the component shafts hand rotated several times on a regular basis.

For equipment **not** manufactured by **Kruger**, refer to the appropriate section in the Installation, Operation and Maintenance Manual to determine the manufacturer's storage requirements.

### **3 c. Equipment Installation**

The Contractor is responsible for installation of Kruger supplied equipment in accordance with the installation instructions.

The Contractor is responsible for proper protection of the equipment during and after installation until this responsibility is taken over by the Owner. This includes covering or wrapping equipment to protect it from water or dust infiltration during the course of installation or construction. Special attention should be paid to ensure that equipment is adequately protected from adjacent construction activity such as welding, concrete finishing, etc. Open conduit or junctions boxes must be covered to ensure that water cannot enter or damage equipment.

The Contractor is responsible for the installation of field electrical and control wiring, including terminations, for all Kruger equipment and control panels. This includes verification that wiring has been correctly installed and terminated prior to requesting Kruger installation inspection services.

The Contractor is responsible for supplying and installing of lubricants in accordance with the manufacturer's recommendations.

### **3 d. Requests for Inspection Services**

Kruger will provide installation inspection services for Kruger supplied equipment and/or systems as required by our purchase agreement with the Contractor. It is the Contractor's responsibility to ensure that all Kruger supplied equipment is installed prior to Kruger's inspection visit. With some installations, a separate Kruger inspection may be required prior to grouting Kruger supplied equipment. It is the Contractor's responsibility to ensure that Kruger inspects and approves the installation prior to addition of the required grout.

Kruger requests a minimum of three weeks notice to schedule installation inspection services, therefore it is essential that the Contractor notify our Project Manager at least three weeks before our personnel are needed on site. Upon receipt of this notice, Kruger's Field Service Manager will schedule our personnel. **However, no Kruger personnel will be dispatched to the jobsite until Kruger receives the**

**completed Pre-Operational Checkout Checklist from the Contractor certifying that the work is complete and ready for Kruger's visit.**

If site readiness requires rescheduling of Kruger's installation or startup visits after the Contractor's formal request, it is the Contractor's responsibility to promptly notify Kruger of the new schedule. Kruger will make every effort to accommodate schedule delays but cannot guarantee availability of installation inspection or startup personnel with less than three week's advance notice.

Sometimes when Kruger personnel arrive on the jobsite as scheduled, we discover that work the Contractor has certified as complete is not yet finished. This causes additional costs and delays and may require additional visits. The Contractor is responsible for any additional costs Kruger incurs as a result.

### **3 e. Contractor Checklists**

Included under Tab 7 of this Briefing Folder are standard Kruger Checklist Forms to be completed by the Contractor and returned to Kruger's Project Manager prior to performance of Kruger's onsite installation inspection services. Kruger will schedule our field service visits prior to return of completed checklists but it is Kruger policy to not dispatch field personnel to the jobsite until the completed and signed checklist is received by our Project Manager or Field Service Manager.

**NOTICE: Kruger policy does not allow Kruger service personnel to perform installation inspections or field start-up until applicable checklist is completed and returned by the Contractor.**



#### **4. Start-Up Planning**

In order for equipment checkout and start-up activities to proceed in an efficient manner, it is essential that the necessary preparatory work is complete prior to Kruger personnel arriving on site. The Contractor, Owner, Engineer, and Kruger should have a common understanding of the activities to be performed on-site and the role each must play.

The Kruger Start-Up Plan for Discfilters consists of two (2) phases. The Pre-Operational Checkout phase is conducted prior to putting the equipment and/or systems on line. The second phase is the Functional (Process) Start-Up phase which occurs when the equipment and/or system is put on line.

The Pre-Operational Checkout is a dry checkout of the equipment; water cannot be in the basins or tanks. During this checkout the installation of the equipment is closely inspected for any problems. At this time Kruger will notify the Contractor of any incomplete work or deficiencies. It is Kruger's policy that field service personnel cannot be dispatched back to the jobsite until we receive the Contractor's confirmation that identified incomplete work or deficiencies have been completed or resolved.

The Functional (Process) Start-Up is when the treatment process is put on line with influent coming into the process and effluent being discharged from the process. Kruger will make the final preparations for equipment operation and will help the operators to optimize the process performance and conduct maintenance and process training during this phase. At this time Kruger considers the facility to be getting beneficial use of the equipment and/or process and the warranty requirements shall apply.

Kruger recommends that a start-up planning conference call involving the Contractor, Owner, Engineer, and Kruger be held approximately 6 to 8 weeks before the Contractor's scheduled process start-up date.

Work that must be completed prior to Kruger's Pre-Operational Checkout visit includes:

- Installation of all Kruger supplied equipment
- Installation and termination of interconnecting wiring between MCCs, control panels, and field instruments for all equipment supplied by Kruger
- Lubrication of all Kruger supplied equipment
- Installation of permanent power to all Kruger supplied equipment.

Work that must be completed prior to Kruger's Functional (Process) Start-Up Checkout visit includes:

- Installation and termination of interconnecting wiring between MCCs, control panels, and field instruments for all equipment that Kruger must communicate with or control
- Removal of all construction debris and flushing of pipelines, etc.
- Installation, operational checkout and wet testing of all upstream and downstream systems necessary to provide inflow to Kruger's system and to handle discharge flows from Kruger's system.
- Installation, operational checkout and wet testing of equipment or systems that are not supplied by Kruger but must be operational to allow completion of Kruger process start-up.
- Identification of the personnel operating the plant during the process start-up and their responsibilities during this phase.
- Scheduling of the training sessions for both maintenance and process training.
- Confirmation of chemicals, power and influent water available to put process on line.

## **5.Contact Information**

Project Manager: Refer to Letter of Introduction

Address: I. Kruger, Inc.  
401 Harrison Oaks Blvd.  
Suite 100  
Cary, NC 27513

Phone: (919) 677-8310

Fax: (919) 677-0082

e-mail:

Field Service Manager: Pete Shelley

Address: I. Kruger, Inc.  
401 Harrison Oaks Blvd.  
Suite 100  
Cary, NC 27513

Phone: (919) 677-8310

Fax: (919) 677-0082

Cell: (919) 522-2506

e-mail: [pete.shelley@veoliawater.com](mailto:pete.shelley@veoliawater.com)

## **6. Requests for Additional Services**

Requests for additional services or services required beyond those stated in our Contract Agreement with the Contractor shall be billed at Kruger's published standard rates. Such additional services may be necessary due to improperly installed equipment, prolonged construction time, or failure to properly coordinate inspection, start-up and training services.

## **7. Checklist Forms**

Attached are the following forms:

Contractor Pre-Operational Checkout Checklist (Form CPO - 4)

Contractor Functional (Process) Start-Up Checklist (Form CFS - 4)

Both forms need to be completed and sent to the Project Manager prior to any Kruger personnel traveling to the project site.

In addition, the Discfilter Installation Checklist is also attached.



## Hydrotech Filter Contractor Pre-Operational Check Out Checklist

Project Name:

Project Number:

Contractor Name:

Name of Person Completing This Form:

Title:

### ITEMS TO BE COMPLETED BEFORE PRE-OPERATIONAL CHECKOUT

- ☐ Contractor shall confirm all mechanical equipment is installed, refer to Installation Manuals.
- ☐ Contractor shall confirm that all control panels are installed.
- ☐ Contractor shall confirm all wires have been pulled and all control panel terminations are complete.
- ☐ Contractor shall confirm all instruments are installed and wires terminated.
- ☐ Contractor shall confirm all piping is complete.
- ☐ Contractor shall confirm all equipment lubricated and greased, refer to Operation & Maintenance Manual.
- ☐ Contractor shall confirm permanent power to all the equipment.
- ☐ Contractor to confirm Electrical Contractor on site and available.

\_\_\_\_\_  
Contractor Signature

\_\_\_\_\_  
Date





I. KRUGER INC.  
401 HARRISON OAKS BLVD, STE 100  
CARY, NC 27513

TELEPHONE 919-677-8310  
FACSIMILE 919-677-0082

## Hydrotech Filter Contractor Functional (Process) Start-Up Checklist

Project Name:

Project Number:

Contractor Name:

Name of Person Completing This Form:

Title:

### ITEMS TO BE COMPLETED BEFORE FUNCTIONAL (PROCESS) START-UP

- ☐ Complete and safe access to the Hydrotech filter system is required prior to start-up. Stairs, platforms, handrails, and grating must be completed prior to start-up.
- ☐ **Contractor shall remove all debris and flush all pipe lines to and from the filter units prior to filling units with water.**
- ☐ Contractor shall confirm that influent water pumping or distribution systems are capable of supplying clarified secondary effluent to the Hydrotech filter at a minimum flow rate equal to one fourth of design flow of one unit for a period of one 8-hour day. For example, if one Hydrotech filter is designed for 4 MGD, Kruger personnel need a continuous flow rate of 1 MGD for one 8-hour day.
- ☐ Contractor shall confirm that systems downstream of the Hydrotech filter are ready to accept water from the filter at a minimum flow rate equal to one fourth of design flow of one filter unit for a period of one 8-hour day.
- ☐ Contractor shall confirm that backwash discharge/disposal systems are ready to accept backwash discharge from the Hydrotech filter.
- ☐ Contractor shall confirm that all deficiencies noted on the attached Kruger checklist(s) have been resolved.

\_\_\_\_\_  
Contractor Signature

\_\_\_\_\_  
Date



## **Discfilter Installation Check List**

- ❑ Discfilters with tank (Type 1F) may be lifted by a forklift or by using a crane and straps. Refer to Operation and Maintenance (O&M) manual
- ❑ Discfilters without tank (Type 2F) may be lifted by a forklift or by using a crane utilizing straps to avoid damaging exposed discs. Refer to Operation and Maintenance (O&M) manual
- ❑ Insure that Covers are mounted on Discfilter. It is necessary to protect the filter from direct sunlight with outdoor installations as the heat and UV-radiation may otherwise damage the filter elements.
- ❑ The Discfilter must be properly leveled. Check and adjust the level of the tank for proper flow at both length and width direction. See installation instructions in O&M. Correct level as necessary.
- ❑ Check security/tighten anchor bolting. Specify anchor size used and Torque  
\_\_\_\_\_.
- ❑ Install a Tank drain valve and piping for tank units or a pump sump for channel-installed units so that the clean water reservoir can be emptied for maintenance.
- ❑ For discfilters without tank (Type 2F), insure the flow opening in the concrete channel wall is at the correct elevation with the SS inlet box.
- ❑ Discfilters without tank (Type 2F) require installation of a gasket/gasket material between the SS inlet channel and concrete wall. The use of corking only as a gasket is not acceptable.
- ❑ During installation of the SS inlet box on Type 2F discfilters (without tanks), inject silicon corking into the lower corners of the inlet box where the gaskets intersects to prevent short circuiting of inlet water
- ❑ Install and check influent piping to discfilter (type 1F discfilters).
- ❑ Install and check Discfilter backwash piping. Backwash piping must have a 1% or greater slope on any pipe section.
- ❑ Install and check effluent piping from Discfilter.
- ❑ Mount Control Panel and make terminations.
- ❑ Install backwash pump on Discfilter, connect piping flanges and hard wire to control panel. Reference O&M Manual.





Kruger, Inc.  
401 Harrison Oaks Boulevard - Suite. 100  
Cary, NC 27513

TELEPHONE 919-677-8310  
FACSIMILE 919-677-0082


- ☐ Wire the service power (in accordance with O&M) to Discfilter control panel. Check power supply.
- ☐ Type 2F filtered water basins; clean basin(s) of all construction debris and dirt.
- ☐ Check the settings of Drum/Disc drive motor protectors against amperage readings on the motors. Tank must be filled with potable or reclaimed water. See Data plate.
- ☐ Check rotation of Drum/Disc drive motor. Rotation indicated on drive motor cover. Turn switch to "manual mode" to operate unit.
- ☐ Check the settings of backwash pump motor protectors against amperage readings on the motors. Tank must be filled with potable or reclaimed water. See Data plate.
- ☐ Check Rotation of backwash pump. Rotation indicated on motor cover. Turn switch to "manual mode" to operate unit.

Contractor/Owner Certification that items were completed according to specifications:

Print  
Name: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

## G. EQUIPMENT VARIATION DETAILS



PIPE GALLERY \*  
NOT REQUIRED


\* Pump Gallery Not  
Required. Backwash  
Piping And Pumps Mounted  
On Filter Chasis.

\* PLEASE REFER TO ATTACHED  
WATER Dwg. 675-220-2F-4-EB  
FOR TYP CONCRETE LAYOUT  
FOR WALKER FILTERS.

NOTES:  
1. SEE SPEC SECTION 05000 FOR CONCRETE  
2. WALKER FILTERS

REVISION MAY 25, 2006

		<b>SONOMA VALLEY COUNTY SANITATION DISTRICT</b>		<b>TERTIARY TREATMENT PLANT UPGRADE ALTERNATIVE "B" FILTER COMPLEX PLAN AT ELEVATION 2'</b>	
DATE	1/4" = 1'-0"	DESIGNED BY	C. OLSON/J. REL	PROJECT NO.	70-12-102.426
DATE	APRIL 2005	CHECKED BY	J. SPORE	SHEET NO.	288 OF 64




Pump Gallery Not Requiring. \*



**HDR**  
HDR Engineering, Inc.

**HDR**  
HDR Engineering, Inc.

[illegible]SONOMA VALLEY COUNTY  
SANITATION DISTRICT


STATUS	AS NOTED
DATE	APRIL 2008
CRIME	J.SPORE

483471	RCE 483471	483471	RCE 483471
483472	RCE 483472	483472	RCE 483472
483473	RCE 483473	483473	RCE 483473
483474	RCE 483474	483474	RCE 483474
483475	RCE 483475	483475	RCE 483475
483476	RCE 483476	483476	RCE 483476
483477	RCE 483477	483477	RCE 483477
483478	RCE 483478	483478	RCE 483478
483479	RCE 483479	483479	RCE 483479
483480	RCE 483480	483480	RCE 483480
483481	RCE 483481	483481	RCE 483481
483482	RCE 483482	483482	RCE 483482
483483	RCE 483483	483483	RCE 483483
483484	RCE 483484	483484	RCE 483484
483485	RCE 483485	483485	RCE 483485
483486	RCE 483486	483486	RCE 483486
483487	RCE 483487	483487	RCE 483487
483488	RCE 483488	483488	RCE 483488
483489	RCE 483489	483489	RCE 483489
483490	RCE 483490	483490	RCE 483490
483491	RCE 483491	483491	RCE 483491
483492	RCE 483492	483492	RCE 483492
483493	RCE 483493	483493	RCE 483493
483494	RCE 483494	483494	RCE 483494
483495	RCE 483495	483495	RCE 483495
483496	RCE 483496	483496	RCE 483496
483497	RCE 483497	483497	RCE 483497
483498	RCE 483498	483498	RCE 483498
483499	RCE 483499	483499	RCE 483499
483500	RCE 483500	483500	RCE 483500


4-17-102.429

TERTIARY TREATMENT PLANT UPGRADE  
ALTERNATIVE "B" FILTER COMPLEX  
SECTIONS AND DETAILS I

		OFFICE OF THE <b>CLERK OF THE CITY OF NEW YORK</b> 100 CITY HALL PLAZA NEW YORK, N.Y. 10037	
DATE 10/10/2019	TIME 10:10 AM	DATE 10/10/2019	TIME 10:10 AM
NAME OF THE PARTY C. OLSON/J. REIL		NAME OF THE PARTY C. OLSON/J. REIL	
ADDRESS 70-12-102,429		ADDRESS 70-12-102,429	
PHONE NO. 298		PHONE NO. 298	
FAX NO. 64		FAX NO. 64	




**PRELIMINARY -  
NOT FOR CONSTRUCTION**  
(DIMENSIONS) SUBJECT TO CHANGE BASED ON FINAL  
CONCRETE DESIGN (BY OTHERS)




**PLAN VIEW**

CERTAIN FILTER COMPONENTS  
HAVE BEEN OBTAINED FROM  
FOR ADDITIONAL DETAILS, REFER TO  
STANDARD DRAWING 675-2220-2F



**SECTION A-A  
SCALE 1 : 48**



**SECTION B-B  
SCALE 1 : 48**



**CONCRETE VOLUMES (APPROX.)**  
1843 CU. FT. (68 CU. YDS) BASED ON 12\"/>

THE PRESENCE OF A PROFESSIONAL ENGINEER'S SEAL ON THIS DRAWING INDICATES THAT A SIGNED AND SEALED ORIGINAL IS ON FILE.

DESIGNER	DATE	TITLE
CDP	05.16.06	DISCHFILTER
DSD	05.16.06	4 UNITS W/INTERNAL BYPASS CHANNEL
PROJECT	DATE	GENERAL LAYOUT
MANAGER	DATE	STANDARD
FILE	DATE	
SCALE	1:36	
PROJECT NO.	675-2220-2F-4-B	
REVISION		
NO.	1	1
BY		

**Krüger**  
401 HARRISON OAKS BLVD DARY, NC 27513  
(919) 677-6310 FAX (919) 677-6380

INTERNAL REF NO: 675-2220-2F-4-B



# INTERNAL HYDRAULIC PROFILE

THE PRESENCE OF A PROFESSIONAL ENGINEER'S SEAL ON THIS DRAWING INDICATES THAT A SIGNED AND SEALED ORIGINAL IS ON FILE.

DESIGNER		DATE		TITLE	
DSD		07/18/05		2216-26/2216/15/26 STANDARD DISC FILTER PANELS MODEL 2216/15	
CDP		07/22/05		CLIENT	
DSD		07/22/05		STANDARD	
BBS		07/26/05		PROJECT NO.	
FILE		1:16		2216-26/26	
SCALE		1:16		SHEET NO.	
1		2		3	

INTERNAL REF NO. \_\_\_\_\_ IF BAR IS NOT "I" ADJUST SCALE ACCORDINGLY

Printed: Tuesday, August 02, 2005 File Name: K:\projects\2216\2216.dwg



**Kruger**

401 HARRISON OAKS BLVD. CARY, NC 27513  
(919) 671-8310 FAX (919) 671-6088

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD

CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1

OF 3

DATE 07/22/05

BY DSD


CHECKED BY BBS

DATE 07/26/05

SCALE 1:16

PROJECT NO. 2216-26/26

SHEET NO. 1



**TABLE 1**

INFLUENT CHANNEL TYPE	BYPASS HT. (mm)
STD. U-SHAPED (EXTERNAL BYPASS)	1460
U-SHAPED (INTERNAL BYPASS)	1355
TYPE 1 / TYPE 2 (INTERNAL BYPASS)	1355

INTERNAL REF. NO. \_\_\_\_\_ IF BAR IS NOT 1" ADJUST SCALE ACCORDINGLY

THE PRESENCE OF A PROFESSIONAL ENGINEER'S SEAL ON THE DRAWING INDICATES THAT A SIGNED AND SEALED ORIGINAL IS ON FILE.

DATE	BY	FOR	DESCRIPTION
07/18/05	PRELIMINARY RELEASE		
07/18/05	DESIGN	DESIGN	
07/18/05	CONSTRUCTION	CONSTRUCTION	

**COMPANY CONFIDENTIAL**

All drawings, plans, specifications, and other documents prepared by or for the undersigned are the property of the undersigned and are not to be distributed, copied, or used in any manner without the written consent of the undersigned. This document is not to be used for any purpose other than that for which it was prepared. The undersigned assumes no responsibility for the accuracy or completeness of the information provided herein.

DESIGNER	CHECKER	DATE	TITLE
DSD	DSD	07/18/05	2216-25/2216/15-2F STANDARD DISC FILTER
CDP	CDP	07/22/05	RIGHT HAND BYPASS INFLUENT BOX
BBS	BBS	07/26/05	STANDARD



QUANTITY	UNIT	SCALE	PROJECT NO.	DATE	REV
124	1:24	2216-25-04	2	2	0

## KRUGER HYDROTECH DISCFILTER EQUIPMENT MAINTENANCE ESTIMATES

### Discfilter Maintenance Estimates: Referenced equipment includes Discfilter units with backwash pump systems

Equipment	Preventive Maintenance requirement	Maintenance Interval	Persons required to perform task	Time required to perform task per unit	Comments
Disc Filter Unit	"Walk By" Inspection	Daily	1	5 min	Walk-by inspection Includes weekly visual inspection of discs and cleaning level sensor, clean/replace clogged nozzles as needed
Motor	Grease Bearings	Every 2 weeks	1	15 min	Expected lifespan of Drive Motor is 10 years
Drive	Check Oil	Every 6 months	1	15 min	
Disc and Drum Seals	Check Seals	Every 6 months	1	2 hours	Drain the filtered water tank and inspect the drum seal and disc seals at the location of attachment to the drum for leakage
Bearings	Inspect Bearings	Every 6 months	1	15 min	Shaft bearing thickness should be at least 3 mm
Bearings	Replace Bearings	Every 10 years	1	4 hours	Typical service life is about 10 years
Nozzles	Check Nozzles for Deterioration and Wear	Annually	1	30 min	Consider replacing every 2 years based on findings
Drive	Change Oil in Gear Box	Every 10,000 hours	1	60 min	Includes the time required for used oil drum handling
Drive Chain	Replace Drive Chain	Every 20 yrs	2	4 hours	Typical service life is about 20 years
Drive Chain	Check Tension and Inspect for Wear	Every 6 months	1	5 mins	
Discs	Replace Filter Panels	~5-10% media replacement every 5-8 yrs unless torn	1	Approx 1 to 1.5 hrs per disc	Typical service life is 5 to 8 years unless torn or physically damaged.
Lip Seals on Drums	Replace Lip Seals	Every 5 years	1	2 hours per unit	Typical service life is 5 years depending on actual filter loading which influences backwash run-time
Backwash Pumps	Replace Seals	Every 5 to 10 years	1	4 hours	Typical service life is 5 to 10 years depending on actual filter loading which influences backwash run-time at design flow



**Krüger**

## *Hydrotech Discfilter*

### *Discfilter Technology Comparison Table Tertiary Applications*

	<u><i>Hydrotech</i></u>	<u><i>AquaDisk</i></u>
<b>Disc Submergence</b>	Partial (55-65%)	Complete
<b>Flow Pattern</b>	Inside out	Outside in
<b>Media</b>	Woven cloth	Non-woven pile
<b>Filtration</b>	10 or 20 micron absolute	10-20 micron average
<b>Acceptable loading rates</b>	5-6.5 gpm/ft <sup>2</sup>	5-6.5 gpm/ft <sup>2</sup>
<b>California Title 22 Approved?</b>	Yes	Yes
<b>Max capacity for a single unit</b>	6.7 mgd	5.5 mgd
<b>Footprint for 7.5 mgd peak flow installation</b>	280 ft <sup>2</sup>	430 ft <sup>2</sup>
<b>Biological fouling of media?</b>	No- Thorough cleaning of media during each backwash	Possible- solids build up can occur over time
<b>Head loss</b>	12" max	12" max
<b>Backwash flow</b>	Counter-current spray	Counter-current vacuum and/or co-current spray
<b>Backwash usage</b>	2-3%	2-8%
<b>Settled solids removal required?</b>	No- Not required, because of inside out flow, all solids are removed during backwash	Yes
<b>Standard material of construction</b>	Stainless steel	Painted steel
<b>Mechanical components</b>	One drive motor and one backwash pump	Multiple valves, backwash pump and sludge removal pump/system
<b>Controls</b>	Simple (Relay Based)	Complex (PLC Based)
<b>Supplied with covers?</b>	Yes	Adder when requested
<b>Maintenance</b>	Simple (All O&M components in dry environment)	Complicated

#### **4. Available Repair and Replacement Services**

Kruger has strategically placed repair and installation personnel across the US, including the state of California.

Kruger also stocks a full line of warranty and replacement parts for the filtration product line in the Cary, North Carolina facility.



I. Krüger Inc.  
401 Harrison Oaks Boulevard - Suite 100  
Cary, NC 27513

TELEPHONE 919-677-8310  
FACSIMILE 919-677-0082

May 31, 2006

Dale Roberts, P.E.  
Sonoma Valley County Sanitation District  
P.O. Box 11628  
Santa Rosa, CA 95406-1628

Re: Sonoma Valley County Sanitation District Substitution Request – Kruger Supplemental Information

Dear Mr. Roberts:

Per our telephone conversation, this letter provides the supplemental data requested along with further clarification on a few items. The supplemental data and clarifications are as follows:

1. Please provide current contact information for five references.

*Kruger Response: We apologize for providing old telephone numbers in the reference list. The updated phone numbers and contacts are as follows:*

Project Name	Contact	Phone
Moncks Corner (Bard), SC	John White	843-568-0960
Hastings WWTP, FL	Joey Lundquist	904-692-1520
Baldwin CDBG WWTP, FL	Don Carey	904-266-5033
Eagle Ridge, FL	Scott Stewart	407-869-1919
Carey Station, GA	Bob Sheldon	770-480-5802
Oconee Crossings WTP - Greensboro, GA	Bob Sheldon	770-480-5802
Palatka WWTP	Platt Drew	386-329-0146
Village of Marissa WTF - Marissa, IL	William Yates	618-781-4295
Marburg (Winder), GA	Leslie Harbin	770-867-4334
City of Mesquite, NV	Bill Tanner	702-346-5237
Alamogordo WWTP, NM	Cheryl Richardson	505-439-1606
N.E. Brunswick County, NC	Michael Painter	910-279-5249

2. Please provide DHS Title 22 acceptance letter and provide clarification on the loading rates.

*Kruger Response: The DHS letter has been attached. The following also provides an updated table with the design criteria for the project.*



I. Krüger Inc.  
401 Harrison Oaks Boulevard - Suite 100  
Cary, NC 27513

TELEPHONE 919-677-8310  
FACSIMILE 919-677-0082

## Hydrotech Discfilter Project Design Table

<b>Peak Flow Rate:</b>	16 MGD (11,120 gpm)
<b>Number of Discfilter units:</b>	4 (3 duty, 1 standby)
<b>Discfilter Model:</b>	HSF2216-2F
Length, ft	14.16
Width, ft	7.48
<b>Drum:</b>	
Material	SS304
<b>Disc:</b>	
Material	ABS
<b>Filter element:</b>	
Frame material	SS304
Filter media	Woven Polyester
Filter pore size, $\mu\text{m}$	10
Number of discs installed per unit	16
Total filter area, $\text{ft}^2$	964
Submerged filter area, $\text{ft}^2$	627
Maximum hydraulic Loading Rate, $\text{gpm}/\text{ft}^2$ – all filters in service	4.4
Maximum Hydraulic Loading Rate, $\text{gpm}/\text{ft}^2$ – one filter out of service	5.9
<b>Drive system:</b>	
Gearbox and motor manufacturer	SEW Eurodrive
Filter motor	1.5 hp, 480V, 3-phase, 60Hz
<b>Back-wash pump:</b>	
Number of pumps	4
Rinse water pump type	Centrifugal - Grundfos
Pump motor	15 hp, 480V, 3-phase, 60Hz
Capacity at 110 psi	106 gpm
<b>Covers:</b>	
Material	Aluminum
<b>Tank:</b>	
Material	Concrete basins (provided by others)

3. Please describe chemical compatibility of the media.

*Krüger Response: The woven polyester media described has the following general characteristics provided by the filter media manufacturer.*

*Biological Resistance: excellent*

*Alkali Resistance: poor*

*Resistant to Mineral Acids: good*

*Resistant to Organic Acids: fair*

*Resistant to Oxidizing Agent: good*

*Effect of Organic Solvent: good*

*UV Resistance: fair*

*Please note that these characteristics are intended to guide laboratory use of the specialized fabric/membrane and as such, provide characteristics of the media in response to high molar concentration of the solvents.*



I. Kruger Inc.  
401 Harrison Oaks Boulevard - Suite 100  
Cary, NC 27513

TELEPHONE 919-677-8310  
FACSIMILE 919-677-0082

*In wastewater practice, with over ten years of experience and hundreds of installations worldwide (over 70 in the US and Canada) Hydrotech Discfilter has established its ability to function in various applications. Kruger has had no issues with the filter media associated with pre-chlorination, coagulation/polymers or other chemical treatment methods.*

If you have any other questions or need further clarifications, please do not hesitate to contact me at the number listed below.

Best regards,

A handwritten signature in black ink, appearing to read "Robert Clay", written over a horizontal line.

Robert Clay  
Regional Product Manager  
(916) 434-6848 Direct

ENC

cc: Steve Garnick - MISCO  
Project File



DIANA M. BONTÁ, R.N., Dr. P.H.  
Director

State of California—Health and Human Services Agency  
**Department of Health Services**



GRAY DAVIS  
Governor

October 2, 2003

Mr. Brian Frewerd  
U.S. Filter-Kruger Products  
401 Harrison Oaks Blvd., Suite 100  
Cary, North Carolina 27513

Subject: Use of the U.S. Filter Kruger Product's Hydrotech polyester media filter utilizing the PET filter fabric to comply with California Water Recycling Criteria

Dear Mr. Frewerd:

By letter dated August 21, 2003, Water 3 Engineering, Inc. requested Departmental review of the U.S. Filter Kruger Product's Hydrotech cloth-media disk filter treatment unit utilizing the PET monofilament filter fabric as an acceptable filtration technology for compliance with the State of California Water Recycling Criteria (Title 22). Accompanying this request was a supplemental report entitled "Evaluation of Hydrotech Filter For Compliance With Title 22 For Recycled water Applications", dated August 2003, which outlined performance evaluation findings using the Hydrotech Filter. The filtration performance data outlined in the report indicates the filter's ability to reliably meet the turbidity performance requirements outlined in Title 22 utilizing the PET monofilament 10-micron filter fabric as the filter medium.

Enclosed for your information are two copies of the Departmental letter dated October 2, 2003, and a copy of the supplemental report. The letter is being sent to you for your information and for your use in your ongoing evaluation of the Hydrotech Filter.



Do your part to help California save energy. To learn more about saving energy, visit the following web site:  
[www.consumerenergycenter.org/flex/index.html](http://www.consumerenergycenter.org/flex/index.html)

Based on a review of the materials submitted, the Department conditionally accepts the use of the U.S. Filter Kruger Product's Hydrotech Filter as a filtration technology for use in compliance with the California Water Recycling Criteria, subject to the following special provisions:

1. Loading rates shall not exceed 6 gpm/ft<sup>2</sup>.
2. Turbidity in the filtered water shall not exceed an average of 2 NTU within a 24-hour period, 5 NTU more than 5 percent of the time within a 24-hour period, and 10 NTU at any time.
3. Acceptance of this technology is contingent on it being complimented with a disinfection process which is compliant with Section 60301.230 (Title 22).
4. Acceptance is for the filter fabric specified as "PET, monofilament, 2:2 twill weave, 11 micron (+/-2.0) mesh opening, 523.2 (n/inch) mesh count, 60-micron thickness, weight rating of 1.48 oz./sq.yd with a stabilized finish" which was assessed in the report noted above. Other cloth materials and fabrication will require additional demonstration studies prior to individual acceptance by the Department.
5. Pretreatment processes should be designed and operated to ensure that the turbidity of the influent to the CMDP does not exceed 10 NTU more than five-percent of the time within a 24-hour period and never exceeds 15 NTU.
6. Individual operations plans shall provide for assurances that adequate backwash duration is practiced to ensure solids removal 'in' and 'on' the filter fabric media.
7. Individual operations plans shall include scheduled inspections and assessments of the cloth condition as an operational safeguard. This should include a routine visual inspection at least monthly, and a more in-depth assessment of the cloth condition at least annually. Inspection frequencies may change as media condition and performance experience is gained with time.

Any proposed changes made in the manufacturing practices that may result in a change in the physical attributes or character of this filter shall be reviewed in advance by the Department to

determine whether the modifications will require additional testing.

The Department will continue to review all proposed water recycling projects on a case-by-case basis to ensure full compliance with all applicable treatment and reliability features required by the Water Recycling Criteria. This will include the collective review of all treatment unit processes, operational controls (e.g. loading rates, backwash/rinse rates, frequency of backwash/rinse, 'O&M' procedures, etc).

If you have any questions concerning this letter, please contact the undersigned at (805) 566-9767.

Sincerely,

A handwritten signature in black ink, appearing to read "Jeff L. Stone". The signature is fluid and cursive, with the first name "Jeff" and last name "Stone" clearly legible.

Jeffrey L. Stone, Chief  
Recycled Water Unit  
Division of Drinking Water  
and Environmental Management

cc: Water 3 Engineering, Inc. - Scott Goldman  
Recycled Water Committee